

FOTENN

540 KING STREET EAST, TOWN OF COBOURG



Prepared for:

**Sunnyside Village Inc.
6849 County Road #10
Port Hope, Ontario
L1A 3V5**

Prepared by:

**FOTENN Planning
+ Design**

**Fotenn Planning + Design
174 Spadina Avenue, Unit 301
Toronto, ON M5T 1X5
fotenn.com**

April 20, 2022

CONTENTS

- 1.0 540 King Street East, Town of Cobourg1
- 2.0 INTRODUCTION2
- 3.0 SURROUNDING AREA AND SITE CONTEXT.....3
- 4.0 PROPOSED DEVELOPMENT5
- 5.0 APPLICATIONS8
- 6.0 SUPPORTING STUDIES9
- 7.0 REVIEW OF POLICY DOCUMENTS 13
 - 6.1 The Provincial Policy Statement (2020)..... 13
 - 6.2 The Growth Plan for the Greater Golden Horseshoe (2020) 19
 - 6.3 Northumberland County Official Plan (2016)..... 21
 - 6.4 Town of Cobourg Official Plan (2018 Consolidation) 24
 - 6.5 Zoning By-law 85-2003 32

- Figure 1: Subject Property.....2
- Figure 2: Site Context.....4
- Figure 3: Site Plan7
- Figure 4: Town of Cobourg Official Plan – Schedule A – Land Use Plan25
- Figure 5: Town of Cobourg Official Plan – Schedule E - Road Network Plan28
- Figure 6: Town of Cobourg Zoning By-Law 85-200332

1.0 INTRODUCTION

Fotenn Planning + Design has been engaged by Sunnyside Village Inc. to prepare a Planning Justification Report for a Zoning By-law Amendment, Draft Plan of Subdivision and Draft Plan of Condominium application to facilitate the redevelopment of their lands for a mixed-use redevelopment featuring residential, commercial, parks and open spaces. Our client's lands are municipally known as 540 King Street East in the Town of Cobourg and are located on the north side of King Street East, south of the Canadian National (CN) and Canadian Pacific Railway (CPR). The subject property has approximately 204 metres of frontage onto King Street East and has a total lot area of approximately 3.97 hectares (refer to Figure 1).

The subject property is currently zoned Rural Exception 3 (RU-3) Zone – Rural Estate Lots for 'Development Area C' under Zoning By-law 85-2003, as amended, and is designated Residential under the Town of Cobourg Official Plan (Consolidated 2018). A Zoning By-law Amendment application is required to implement the proposed development. The purpose of this report is to assess the appropriateness and planning merits of the applications required to facilitate the proposed development.



Figure 1: Subject Property

Fotenn submitted three preliminary concepts to the Town for their review and feedback as part of a pre-consultation process. Town staff provided detailed comments on the concepts on November 21, 2019, which were favourable to the proposed conservation of on-site heritage properties, the introduction of a private right-of-way, and the integration of a diverse housing mix.

The concept plan was revised accordingly to reflect the comments made by the Town and the proposed application implements the updated concept plan. In addition, the pre-consultation letter outlined the materials required for a complete application. In accordance with the Town's requirement the following supporting documents have been submitted to the Town as part of the application:

- 1) Planning Justification Report
- 2) Urban, Landscape & Sustainable Design Study
- 3) Architectural Development Concept Plan
- 4) Conceptual 3D Massing
- 5) Architectural Conceptual Elevations
- 6) Architectural Conceptual Perspectives
- 7) Draft Plan of Subdivision/Condominium
- 8) Functional Servicing Report (FSR)
- 9) Stormwater Management Report (SWM)
- 10) Tree Inventory, Assessment and Preservation Report
- 11) Traffic Impact Study
- 12) Cultural Heritage Impact Brief
- 13) Archaeological Resource Assessment
- 14) Environmental Impact Study
- 15) Noise and Vibration Impact Study
- 16) Topographical Survey
- 17) Geotechnical Investigation Report
- 18) Environmental Site Assessment Phase 1
- 19) Environmental Site Assessment Phase 2

2.0

SURROUNDING AREA AND SITE CONTEXT

The subject property is municipally known as 540 King Street East and is located in the Town of Cobourg, identified as an Urban Area within the County of Northumberland. The subject property is legally described as Part of Lot 10, Concession A (Geographic Township of Hamilton, Town of Cobourg, County of Northumberland). The property currently contains a two-storey dwelling and barn and silos, surrounded by associated agricultural land. A wetland is located in the north west corner of the property and is partially located within the unopened road allowance.

The surrounding area comprises of the following:

North: The Canadian Pacific & Canadian National Railway corridor and rural/agricultural land further north.

South: King Street East right-of-way (County Road 2) and a proposed commercial development which consists of three retail buildings, one which includes a drive-through.

West: An unopened road allowance for the future extension of Willmot Street north as an overpass to the railway corridor. Further west is the site of a recently approved residential development (East Village Phase 5) which includes an apartment block, 10-plex units, townhouses, semi-detached and detached homes.

East: An existing low-rise residential dwelling. There appears to be an environmental constraint that traverses the property along the eastern property line.

The subject property is serviced with community amenities including parks along the Lake Ontario shoreline, schools, commercial uses and transit (refer to Figure 2). A cluster of employment uses is located south of the subject property providing employment opportunities for nearby residents. The subject property is immediately accessible by public transit with the Cobourg Transit Route 1 bus stop located within 100 metres, providing access

to Downtown Cobourg, the Lake Ontario shoreline and residential communities to the west. Additionally, access to Cobourg Transit provides opportunities for residents to connect to regional transit including the VIA Rail from the Cobourg Train Station. The subject property is also within walking distance of recreational trails along the lake at Lucas Point Park and Fitzhugh Shores Park.

The subject property is located along the King Street East arterial road which provides access to Downtown Cobourg where there is a concentration of commercial, institutional and cultural uses. Further, there are two existing schools, Brookside Secondary School and Merwin Greer School, to the west that are approximately 1 km from the subject property.




Figure 2: Site Context

3.0 PROPOSED DEVELOPMENT

The proposed development contemplates the subdivision of the 3.97 hectare site to provide 90 residential units including a retained residential farmhouse and barn. The proposal introduces a new residential community comprised of residential, mixed-use and open space uses. The retained barn will present a future opportunity to incorporate commercial community amenity uses.

Built Form

The proposed development includes 6 new single-detached units, 4 semi-detached units, 55 townhouse units (8 rear lane townhouses with attached garages, 17 rear lane townhouses with detached garages and 30 stacked townhouses), and 24 mixed-use units within five blocks organized by a looped internal common element private road.

The single-detached units are proposed to be 2 storeys in height, the semi-detached units are proposed to be 2 storeys in height, the townhouse units are proposed to be 2-3 storeys in height, the stacked units are proposed to be 4 storeys in height and the mixed-use units are proposed to be 3 storeys in height.

The proposed buildings are arranged with those of higher density and mixed uses oriented towards the primary frontage at King Street East and transitioning down towards the interior and rear. Behind the mixed-use buildings located along the property's south boundary, a row of stacked townhouses is proposed with their primary frontage oriented towards the internal common element road. Detached garages are accessed from a rear-access laneway. Within the central block bounded by the internal common element private road are a mix of single-detached, semi-detached and townhouse units. The single-detached and semi-detached units feature a combination of front and rear access garages, while the townhouses feature rear-access attached garages. Along the northern property line is a row of townhouse units with detached rear-access garages serving as a buffer between the townhouses, acoustic berm and railway line. A 30m buffer provides appropriate separation distance between the rail line and building edge of the rear townhouses.

Heritage

The former residential farmhouse, barn and associated silos are proposed to be retained and serve as a key focal point for the new neighbourhood, celebrating its rural heritage. The retained barn will be restored and presents opportunities to be adaptively reused as a commercial community amenity area, and the former residential farmhouse will be renovated for continued residential use. Potential opportunities to use the silos as canvas for public art are being considered. Both retained structures are located on separate blocks within the development which ensures its visual prominence throughout the community.

Environmental/Open Space

The north west portion of the site has limited development potential because of an identified wetland area and embankment reserved for a future road allowance for the anticipated northern extension of Willmott Street over the railway. This environmental constraint creates new opportunities to propose a naturalized restoration area and multi-use trail along the western edge of the subject lands. The open space provides for the protection of the environmental area and features a strong interface with the residential townhouses at the west portion of the site. Further, the landscaped amenity area provides appropriate separation of residential uses from the future road extension.


Additional parks and open spaces anchor various portions of the site. These include the Central Park sited around the retained former farmhouse which serves as the primary entrance gateway into the community. The design of the Central Park intends to conserve views to the retained residential farmhouse from King Street East. A parkette adjacent to the retained barn structure is envisioned to be used as a flexible space for community gatherings, programming and commercial uses. Opportunities for programming may include farmer's markets and community festivals. The barn parkette area offers additional space onto which future commercial community uses can expand during the warm weather months of the year.

Road network

The internal road network has been designed with a complete streets approach which prioritizes pedestrian safety and active transportation activities. Wide streets featuring a curved design, sidewalks, on street parking, painted sharrows (shared lane pavement markings), and multiple mid-block connections accommodating pedestrian, cycling and vehicular movement encouraging active transportation methods. On the east side of the internal road, an extension branches off towards the east property line, providing opportunities to connect to a future development on the abutting property. Street trees are proposed to be planted at regular intervals on the King Street East frontage which frames the north side of the street and creates an inviting appearance to the neighbourhood. Street trees are also proposed along the internal road system to create an inviting and green community. The internal road system establishes a well-connected network of streets with identifiable edges and a centre as a key element in the delivery of a compact community.

A small network of laneways connected to the internal road is proposed to provide access to residents' and commercial visitors parking needs.

122 parking spaces for residential uses are proposed throughout the subject lands. Three surface parking areas with a total of 38 parking spaces for commercial uses are proposed along the King Street East frontage and beside Central Park. 45 visitor parking spaces are proposed through on-street parking and alongside the resident parking at the rear townhouses. Finally, 49 visitor parking spaces are provided for the retained barn area at the north east portion of the site, thereby exceeding all required parking standards for the proposed development.



SITE INFORMATION

SITE AREA
Total Site Area: 3.97he

PARKING RATES REQUIRED
Residential (Detached, Semi-detached): 2.0 p/unit
Residential (Townhouses): 1.0 p/unit
Mixed-Use: 1.0 p/unit
Retail: 3 p/100m² GFA

SETBACKS F.Y. C.Y. S.Y. R.Y.
Detached: 4.5m 2.4m 1.2m 7.5m
Semi-Detached: 4.5m 2.4m 1.2m 7.5m
Townhouses: 4.5m 2.4m 1.2m -
Mixed-Use: 1.8m 1.8 0m -

DEVELOPMENT STATISTICS

RESIDENTIAL UNITS
Detached: 7
Semi-Detached: 4
Townhouses: 55
Mixed-Use: 24
TOTAL: 90

PARKING Required Provided
Residential: 87 118
Visitor: 22 33
Commercial: 36 38
Subtotal: 145 190

Mixed Use Barn Structure: 49
Total: 239

OPEN SPACE
Environmental Restoration Zone: 0.255ha
Central Park: 0.136ha
Barn Plaza: 0.085ha

Sunnyside Village
540 King St,
Cobourg
Concept Plan



- LEGEND**
- PROPERTY BOUNDARY
 - ENVIRONMENTAL ZONE AND BUFFER
 - FUTURE ROAD ROW WIDENING
 - UNOPENED ROAD EMBANKMENT

No.	REVISION	DATE	BY
9	REVISED CONCEPT PLAN	2022.04.07	UMG
8	REVISED CONCEPT PLAN	2022.03.29	UMG
7	REVISED CONCEPT PLAN	2022.02.22	UMG
6	REVISED CONCEPT PLAN	2022.02.18	UMG
5	REVISED CONCEPT PLAN	2021.09.08	TK
4	PREFERRED CONCEPT PLAN	2021.06.18	TK
3	CONCEPT PLAN	2021.05.11	TK
2	CONCEPT PLAN	2021.04.23	TK
1	BASE PLAN	2021.04.07	TK

CLIENT
SUNNYSIDE VILLAGE INC.

FOTENN
Planning + Design

174 Spadina Avenue, Suite 304 Toronto, ON
616.789.4530 www.fotenn.com

DESIGNED: TK/UMG
REVIEWED: UM
DATE: 2022.04.07

P1

Figure 3: Site Plan

4.0 APPLICATIONS

The applications required to facilitate the proposed development include:

- / Zoning By-law Amendment
- / Draft Plan of subdivision
- / Draft Plan of Condominium
- / Part Lot Control Application
- / Site Plan Control Application

Draft Plan of Subdivision: The Draft Plan of Subdivision will implement the intended block plan comprised of a total thirteen (13) blocks. The block plan features the following:

Block	Use	# of units
Block 1	Mixed-use	8
Block 2	Mixed-use	8
Block 3	Mixed-use	8
Block 4	Residential (Stacked Towns)	18
Block 5	Residential (Heritage)	1
Block 6	Residential (Stacked Towns)	12
Block 7	Residential (Single and Semi-detached)	10
Block 8	Residential (Towns)	8
Block 9	Residential (Towns)	17
Block 10	Mixed-Use Barn (Heritage)	N/A
Block 11	Embankment (Future road allowance)	N/A
Block 12	Future Road Widening	N/A
Block 13	Common Elements Area (road, commercial/visitors parking, parks)	N/A

Zoning By-law Amendment: The Zoning By-law Amendment has been prepared to implement the above noted Draft Plan of Subdivision. The amendment seeks to rezone the property under Zoning By-law 85-2003 from Rural Exception 3 – Rural Estate Lots for “Development Area C” to site-specific Neighbourhood Residential exception zone (NR2-xx), Neighbourhood Mixed Use exception zone (NMU-xx), Residential 4 exception zone (R4-xx), Environmental Constraint Zone (EC) and Open Space Zone (OS) to permit the proposed land uses and provide for appropriate performance standards to accommodate the proposed development.

A detailed zoning table that identifies the relief required for the proposed site-specific zoning is included in section 6.5 of this Planning Justification Report.

Draft Plan of Condominium: The Draft Plan of Condominium seeks to create two types of condominium tenure for the subject lands. The entire property shall be registered as a Common Elements Condominium comprised of shared elements including the private road, commercial visitors parking, central park, parkette, residential visitor parking, community mailbox areas, and the environmental restoration zone. The mixed-use buildings and stacked townhouse will be registered with a Standard Condominium which will be nested within the broader Common Elements Condominium to facilitate units which are vertically and horizontally separated. The subdivision plan will facilitate the creation of a condominium with parcels of tied land (POTL) for the detached, semi-detached, townhouse blocks and the mixed-use barn structure. The plan will also facilitate the creation of a condominium for the stacked townhouses and mixed-use buildings.

Part Lot Control Application: A future Part Lot Control application will be submitted to create the individual parcels of tied land (POTL) to facilitate the townhouse, single-detached and semi-detached buildings.

Site Plan Application: A Site Plan application will be required and will be submitted at a later date.

5.0 SUPPORTING STUDIES

In addition to this Planning Justification Report, the following materials are being submitted in support of the Zoning By-law Amendment application. The findings are summarized below:

Geotechnical Investigation Report:

The Geotechnical Investigation Report prepared by GHD dated April 7, 2022 found that the site is generally covered with topsoil that is underlain by deposits of silty sand and then native glacial till. The assessment finds that there will not be significant constraints for the proposed residential development from the seasonal variations of groundwater as the water can be handled with appropriate engineering techniques. The report finds that it is expected that groundwater will generally be below the depth of the future development, although seepage may be encountered in deeper excavations or foundations. Seepage is expected to be seasonal in nature. If short-term pumping of groundwater at volumes greater than 50,000 L/day and less than 400,000L/day is required during the construction stage, the EASR must be completed. In summary, the proposed mixed-use development is suitable from both a hydrogeologic and geotechnical perspective.

Further, the report states that minor impacts are expected to groundwater and surface water as a result of the future development provided that appropriate planning such as the incorporation of LIDs), mitigation measures and proper construction techniques are considered.

The report concludes that from a geotechnical perspective, the site is suitable for construction of the proposed development including up to four-storey buildings, associated servicing, paved access roads and parking.

Phase 1 Environmental Site Assessment:

The Phase 1 Environmental Site Assessment (ESA) prepared by GHD dated April 23, 2020 identified potentially contaminating activities (PCAs) within the Phase 1 Study Area, which in GHD's opinion has resulted in areas of potential environmental concern (APECs) on the property. The PCAs within the Phase 1 Study Area were identified for an adjacent active rail line and manufacturing operations, but not on the property itself. The assessment recommends that further environmental investigation in the form of a Phase 2 Environmental Site Assessment is warranted to investigate the risks of impact of the identified APECs to the property.

Phase 2 Environmental Site Assessment:

The Phase 2 ESA was prepared by GHD dated May 24, 2020 based on the results of the Phase 1 ESA. The Phase 2 ESA investigated the subsurface through advancing 10 boreholes to collect soil and groundwater samples. Monitoring wells were installed in three (3) of the boreholes. The field investigations conducted as part of Phase 2 concluded that all soil tested from the Property meets the MECP Table 2 Standards for residential property use for the parameters tested. Further, groundwater tested from the property meets the MECP Table 2 Standards for all property use for the parameters tested.

The report concludes that based on the observations, it is their opinion that there is a low level of concern at the property from an environmental perspective and is suitable for the proposed residential development. The report stated that no further environmental evaluation is required at this time.

Cultural Heritage Impact Assessment:

The Heritage Impact Assessment (HIA) prepared by Martindale Planning Services dated April 5, 2022 addresses the impact of the proposed development on recognized on-site heritage resources. The property at 540 King Street East is Listed on the Town of Cobourg Heritage Register of Properties of Cultural Heritage Value and Interest (Not Designated). The HIA states that the existing residential farmhouse includes some historical elements which

should be preserved. The barn structure is in fair condition and requires extensive refurbishment to be able to be used as an occupiable space, including restoration of the exterior brick walls and replacement of the roof between the silos and barns. The HIA states that the variety of new residential buildings proposed for the site preserve the heritage elements of the original home and barn and is a positive example of redevelopment within the Town of Cobourg. Further, the HIA states that the proposed residential buildings are appropriately situated around the heritage buildings and will not adversely impact the heritage significance of the on-site resource. The HIA makes the following recommendations:

- The subject property be designated under Part IV of the Ontario Heritage Act for its cultural heritage significance;
- A Conservation Plan outlining the manner in which the dwelling and barn are to be rehabilitated without losing their key heritage attributes be prepared;
- A suitable plaque be installed in front of the retained buildings.

Noise and Vibration Study:

A Noise and Vibration Study was prepared by Pinchin Ltd., dated February 28, 2022 for the proposed residential development which assessed the noise and vibration impacts of road and rail traffic activity. The vibration measurement results show that the vibration impact is within the acceptable range as outlined in the FCM/RAC, CP/CN publications. Vibration mitigation measures such as special vibration isolation foundations are therefore not required as part of the proposed development. Further, the feasibility study reviewed the potential noise impacts of nearby stationary sources on the proposed project and the proposed project on the existing community. The noise impacts were found to be within acceptable limits as defined in MECP Publication MPC 300.

With regards to road and rail traffic noise impacts on the proposed development, the report outlines applicable noise control measures so that the MECP road and rail noise guidelines can be met at affected facades and outdoor locations. For the barn parkette area, an acoustic barrier is recommended at the east property line. While sound levels may still exceed the applicable daytime limit, the location of the barrier was selected to maximize public enjoyment of the barn parkette open space, aligned with CPTED principles and promote overall good place-making. For the Central Park area, while an acoustic barrier can mitigate the identified road traffic noise, it is not recommended to be erected in order to preserve the cultural heritage value of the retained residential farmhouse which requires an unobstructed view through the Central Park.

Functional Servicing Report

A Functional Servicing Report dated March 2022 was prepared by D.M. Wills to determine the feasibility of the proposed development with respect to sanitary and water servicing of the subject lands. The report concludes that the requirements of site servicing are met in accordance with municipal and provincial guidelines. The report indicates that the site can be serviced as follows:

- Storm sewers for the minor storms will convey flows on-site in conjunction with D.M. Wills' Preliminary Stormwater Management Design and discharge to municipal infrastructure in the King Street right-of-way.
- Sanitary servicing will be provided through a connection to the 375mm diameter trunk main in Willmott Street.
- Water Servicing will be provided through a connection to the 300mm diameter water main stub at King and Willmott Street and will include on-site looping.

Stormwater Management Report

A Preliminary Stormwater Management Plan and Report was prepared by D.M. Wills, dated February 2022, to evaluate the impact of the proposed development on stormwater runoff. As the proposed site development will

alter existing drainage patterns, a preliminary stormwater management plan was developed that permits the development to proceed without adverse impacts to the receiving drainage systems.

The report outlined a combination of low impact development considerations and stormwater quality controls to achieve “Enhanced” Level 1 protection as defined in the Stormwater Management Planning and Design Manual. The stormwater quality control measures are required as part of the development to ensure the receiving drainage system will not be adversely affected. These control measures will be provided by a combination of low-impact development features and oil-grit separator structures.

Environmental Impact Study

A Scoped Environmental Impact Study (EIS) was prepared by Pinchin Ltd., dated March 29, 2022, for the subject property. The report was prepared to: identify natural heritage features present on or immediately adjacent to the Site and characterize their ecological functions, evaluate the environmental effects of the development proposal that might reasonably be expected to have an impact on the natural features, and provide recommendations of mitigation measures to avoid or minimize the potential impacts.

The EIS report identified direct and indirect impacts on the natural environment as a result of the proposed development. To mitigate or avoid these impacts, the report identifies mitigation measures and recommendations to be implemented prior to the commencement of onsite development work such as exclusion fencing to sensitive natural features and setbacks from the wetland areas. The EIS provides further detailed recommendations as they relate to tree vegetation removal, erosion and sediment control, wildlife and species at risk encounter protocol and restoration and enhancement.

The report concludes that the ecological functions of the adjacent natural features can be preserved and the natural landscape will be enhanced through appropriate implementation of the proposed environmental plan and proposed Restoration Plan.

Archaeological Resource Assessment

A Stage 1 Archaeological Resource Assessment was prepared by Earthworks Archaeological Services, dated March 16, 2022 for the proposed development identified features indicating archaeological potential. The location of the site adjacent to King Street East, which historical maps suggest functioned as a historic transportation route, location of the site adjacent to the historic Grand Trunk Railway, location of a historic structure on site, and location of the study area within 97m of an unnamed creek, were identified as features with potential archaeological potential through the background investigation.

As a result of the identification of these features, the assessment determined that the study area contains archaeological potential and a Stage 2 archaeological assessment is recommended.

Urban, Landscape & Sustainable Design Study

The Urban, Landscape & Sustainable Design Study prepared by Fotenn Planning & Design, dated April 2022 evaluates the proposed development against the relevant municipal urban design framework, as well as the One Planet Living framework. One Planet Living is a sustainability framework which can be applied as best practices for community master planning.

The Design Study outlines how the proposed development meets provincial policy objectives of building complete neighbourhoods. Further, the Study outlines how the proposal is aligned with the community design policies of Section 5 of the Official Plan. Utilizing the One Planet Living Principles, the Study demonstrates that the new development will offer a compact and accessible new development that creates varied living opportunities. The Study finds that the proposal respects the site’s cultural heritage and accommodates active transportation through

the well-connected network of streets and trails. The proposed parks, public spaces and naturalized areas prioritizes and celebrates ecological functionality and sustainability.

Draft Plan of Subdivision/Condominium

The M-Plan was prepared by DFP Surveyors dated April 2022. It is proposed to register a plan of subdivision to create 13 blocks to accommodate 90 residential units, common elements areas, mixed-use barn structure, a future road widening at King Street East, and embankment area for the future road allowance for the extension of Willmott Street.

Tree Inventory, Assessment and Preservation Report

The Tree Inventory, Assessment and Preservation (TIPP) Report dated March 2022 prepared by Pinchin Ltd., provided an inventory of all existing trees equal to or greater than 30cm diameter at breast height on and within 6m of the site, as well as protection recommendations for retainable trees. The report indicates that all trees on the subject site are to be removed other than a few in the area proposed to be preserved as a wetland.

The TIPP drawing identifies trees within the Central Park area with the potential to be conserved. The trees in this area may be retained or removed pending further details of the stormwater management strategy which shall be explored during the Site Plan phase.

Traffic Impact Study

A Traffic Impact Study was prepared by BA Group, dated March 2022 for the proposed development which provided an assessment of traffic operations in the study area. The report indicates that King Street East currently has 400 and 475 two-way vehicles/hour in front of the site during AM/PM peak hours, respectively, and that anticipated site traffic is estimated to be 50 and 55 two-way vehicle trips during the AM/PM peak hours, respectively.

Further, the report findings indicated the following driveway operations in the surrounding intersections:

- a. Maplewood Boulevard / King Street East is expected to experience a Level of Service (LOS) of E or better during all peak hours.
- b. Willmott / King Street East is expected to experience a Level of Service (LOS) of C or better during all peak hours.
- c. Site Entrance / King Street East is expected to experience a Level of Service (LOS) of C or better during all peak hours.

The Traffic Impact Study concludes that the proposed development can be reasonably accommodated within the Town's existing and future road network.

6.0 REVIEW OF POLICY DOCUMENTS

6.1 The Provincial Policy Statement (2020)

The Provincial Policy Statement (“PPS”), 2020, provides policy direction on matters of provincial interest related to land use planning and development to enhance the quality of life for all Ontarians. The PPS also provides guidance with respect to building strong communities through the efficient use of land and resources while protecting the quality of the natural environment and public health and safety. The *Planning Act* requires that all decisions affecting land use planning matters to be consistent with the policy statements issued under the *Act*. This section provides a discussion of the relevant policies in the PPS (2020) applicable to the proposed development.

Section 1 of the PPS provides direction on building strong healthy communities. Section 1.1.1 of the PPS contains policies relating to the sustainability of healthy, livable and safe communities, and states:

“1.1.1 Healthy, liveable and safe communities are sustained by:

- a) promoting efficient development and land use patterns which sustain the financial well-being of the Province and municipalities over the long term;*
- b) accommodating an appropriate affordable and market-based range and mix of residential types (including single-detached, additional residential units, multi-unit housing, affordable housing and housing for older persons), employment (including industrial and commercial), institutional (including places of worship, cemeteries and long-term care homes), recreation, park and open space, and other uses to meet long-term needs;*
- c) avoiding development and land use patterns which may cause environmental or public health and safety concerns;*
- d) avoiding development and land use patterns that would prevent the efficient expansion of settlement areas in those areas which are adjacent or close to settlement areas;*
- e) promoting the integration of land use planning, growth management, transit-supportive development, intensification and infrastructure planning to achieve cost-effective development patterns, optimization of transit investments, and standards to minimize land consumption and servicing costs;*
- f) improving accessibility for persons with disabilities and older persons by addressing land use barriers which restrict their full participation in society;*
- g) ensuring that necessary infrastructure and public service facilities are or will be available to meet current and projected needs;*
- h) promoting development and land use patterns that conserve biodiversity; and*
- i) preparing for the regional and local impacts of a changing climate.”*

The proposed development promotes an efficient form of development and land use pattern within the Urban Settlement Area Boundary, adjacent to existing developments. The redevelopment of an underutilized parcel of land into a new neighbourhood efficiently utilizes existing municipal services (waste and wastewater) along King Street East while minimizing servicing costs. The proposed development introduces a wide range of housing forms ranging from single and semi-detached houses, townhouses and stacked townhouses, as well as new parks and open spaces which aim to meet the Town’s long-term needs. The proposed development is in close proximity to existing community uses such as schools and trails along the Lake Ontario shoreline. Finally, the proposed development promotes development and land use patterns that conserve biodiversity through the protection and enhancement of the wetland feature in the west portion of the subject property, which is adjacent to a proposed multi-use trail.

The PPS also states:

“1.1.2 Sufficient land shall be made available to accommodate an appropriate range and mix of land uses to meet projected needs for a time horizon of up to 25 years, informed by provincial guidelines. However, where an alternate time period has been established for specific areas of the Province as a result of a provincial planning exercise or a provincial plan, that time frame may be used for municipalities within the area.

Within settlement areas, sufficient land shall be made available through intensification and redevelopment and, if necessary, designated growth areas.

Nothing in policy 1.1.2 limits the planning for infrastructure, public service facilities and employment areas beyond a 25-year time horizon.”

The proposed development assists in providing residential intensification within the Town of Cobourg’s Built Boundary of the Urban Settlement Area Boundary as identified on Schedule A of the Official Plan, which is consistent with the PPS. The proposed development creates a new compact neighbourhood which contributes to the existing housing stock within the settlement area and assists in meeting the projected needs of the community.

The subject property is located within the Built boundary of the Town of Cobourg’s Urban Settlement Area. Section 1.1.3 of the PPS states:

“1.1.3.1 Settlement areas shall be the focus of growth and development.

1.1.3.2 Land use patterns within settlement areas shall be based on densities and a mix of land uses which:

- a) efficiently use land and resources;*
- b) are appropriate for, and efficiently use, the infrastructure and public service facilities which are planned or available, and avoid the need for their unjustified and/or uneconomical expansion;*
- c) minimize negative impacts to air quality and climate change, and promote energy efficiency;*
- d) prepare for the impacts of a changing climate;*
- e) support active transportation;*
- f) are transit-supportive, where transit is planned, exists or may be developed; and*
- g) are freight-supportive.*

Land use patterns within settlement areas shall also be based on a range of uses and opportunities for intensification and redevelopment in accordance with the criteria in policy 1.1.3.3, where this can be accommodated.”

1.1.3.3 Planning authorities shall identify appropriate locations and promote opportunities for transit-supportive development, accommodating a significant supply and range of housing options through intensification and redevelopment where this can be accommodated taking into account existing building stock or areas, including brownfield sites, and the availability of suitable existing or planned infrastructure and public service facilities required to accommodate projected needs.”

The proposed development provides for growth and development within the Urban Settlement Area which is consistent with the PPS. The proposed new neighbourhood provides for a cost-effective pattern of development through the compact redevelopment of an underutilized parcel of land. The proposed development will make use of existing municipal services (water and wastewater) along King Street East as well as existing public service facilities including schools and recreational trails. The proposed development assists in promoting active transportation through introducing a multi-use trail and cycling infrastructure such as painted sharrows. The pedestrian-oriented design of the internal road network and proposed mixed-use buildings along the King Street East frontage further support a pedestrian-friendly environment. Additionally, the proposed development is located

within 100 metres of a bus transit stop for Route 1 on the Cobourg Transit, which reflects transit-supportive development.

The proposed development is an example of intensification which takes into account the emerging patterns of development in the surrounding area. West of the subject lands is the site of an approved development for East Village (Phase 5), a new residential community which will consist of an apartment block, multiplex units, townhouses, semi-detached and detached homes. The proposed development is in keeping with the emerging pattern of compact development which optimize existing infrastructure.

The PPS also states:

“1.1.3.6 New development taking place in designated growth areas should occur adjacent to the existing built-up area and should have a compact form, mix of uses and densities that allow for the efficient use of land, infrastructure and public service facilities.”

The proposed development is located in the Built Boundary of the Urban Settlement Area Boundary. The proposed development promotes an efficient development and land use pattern by providing for the redevelopment of an underutilized parcel of land with a more compact form adjacent to areas with emerging development. The development also makes efficient use of existing infrastructure through proposing intensification along the King Street East arterial road.

Section 1.3 of the PPS provides direction related to employment, and states:

*“1.3.1 Planning authorities shall promote economic development and competitiveness by:
d) encouraging compact, mixed-use development that incorporates compatible employment uses to support liveable and resilient communities, with consideration of housing policy 1.4.”*

The proposed development contributes to the Town’s economic development through the introduction of compact mixed uses along the King Street East frontage, supporting liveable and resilient communities within the Town.

Section 1.4 of the PPS provides direction on the appropriate range and mix of housing types and densities required to meet projected requirements of current and future residents, and states:

“1.4.1 To provide for an appropriate range and mix of housing options and densities required to meet projected market-based and affordable housing needs of current and future residents of the regional market area by:

- a) maintain at all times the ability to accommodate residential growth for a minimum of 15 years through residential intensification and redevelopment and, if necessary, lands which are designated and available for residential development; and*
- b) maintain at all times where new development is to occur, land with servicing capacity sufficient to provide at least a three-year supply of residential units available through lands suitably zoned to facilitate residential intensification and redevelopment, and land in draft approved and registered plans.*

1.4.3 Planning authorities shall provide for an appropriate range and mix of housing options and densities to meet projected market-based and affordable housing needs of current and future residents of the regional market area by:

- a) establishing and implementing minimum targets for the provision of housing which is affordable to low and moderate income households and which aligns with applicable housing and homelessness plans. However, where planning is conducted by an upper-tier municipality, the upper-tier municipality in consultation with the lower-tier municipalities may identify a higher target(s) which shall represent the minimum target(s) for these lower-tier municipalities;*
- b) permitting and facilitating;*

1. all housing options required to meet the social, health, economic and well-being requirements of current and future residents, including special needs requirements, and needs arising from demographic changes and employment opportunities; and
 2. all types of residential intensification, including additional residential units, and redevelopment in accordance with policy 1.1.3.3;
- c) directing the development of new housing towards locations where appropriate levels of infrastructure and public service facilities are or will be available to support current and projected needs;
- d) promoting densities for new housing which efficiently use land, resources, infrastructure and public service facilities, and support the use of active transportation and transit in areas where it exists or is to be developed; and
- e) requiring transit-supportive development and prioritizing intensification including potential air rights development, in proximity to transit, including corridors and stations; and
- f) establishing development standards for residential intensification, redevelopment and new residential development which minimize the cost of housing and facilitate compact form, while maintaining appropriate levels of public health and safety.”

The proposed development contributes a wide range of housing options and densities including single-detached houses, semi-detached houses, townhouses, stacked townhouses and mixed-use buildings, which appropriately facilitate residential intensification to assist in meeting projected regional housing needs for current and future residents. Further, the proposed development represents an appropriate form of residential intensification within the Town of Cobourg’s Urban Settlement Area, through making efficient use of existing infrastructure and public facilities such as the existing Cobourg Transit bus route, schools, churches and surrounding commercial services.

Section 1.5 provides direction on Public Spaces, Recreation, Parks, Trails and Open Space, and states:

“1.5.1 Healthy, active communities should be promoted by:

- a) *planning public streets, spaces and facilities to be safe, meet the needs of pedestrians, foster social interaction and facilitate active transportation and community connectivity;*
- b) *planning and providing for a full range and equitable distribution of publicly-accessible built and natural settings for recreation, including facilities, parklands, public spaces, open space areas, trails and linkages, and, where practical, water-based resources;*
- c) *providing opportunities for public access to shorelines; and*
- d) *recognizing provincial parks, conservation reserves, and other protected areas, and minimizing negative impacts on these areas.”*

The proposed development promotes healthy and active communities through the introduction of three new parks and open spaces integrated throughout the proposed community. At the west portion of the property, the proposed restoration area with multi-use trail and preservation of the wetland feature provides recreational opportunities and a landscaped amenity area next to naturalized areas for residents. Additional parks and open spaces are proposed within the subject lands such as the parkette adjacent to the retained barn structure, as well as the Central Park which surrounds the former residential farmhouse, which together foster social interaction within the community. Finally, the new community is arranged around a looped internal private road network that contains sidewalks and a wider cross section which facilitates active transportation among residents and the wider community.

Section 1.6 provides provincial direction on Infrastructure and Public Service Facilities. The PPS states:

“1.6.6.2 Municipal sewage services and municipal water services are the preferred form of servicing for settlement areas to support protection of the environment and minimize potential risks to human health and safety. Within settlement areas with existing municipal sewage services and municipal water services,

intensification with redevelopment shall be promoted wherever feasible to optimize the use of the services.”

The subject property is located within the Built Boundary of the Urban Settlement Area, which contains existing piped water and sewer services. Given the compact nature of the proposed development and the location of existing municipal services (waste and wastewater) along King Street East, the proposed development can be adequately serviced by existing infrastructure, minimizing the servicing costs and supporting the protection of the environment. The Functional Servicing Report prepared by D.M. Wills demonstrates that the proposed development will be serviced by water and sanitary services and municipal storm sewers that are currently available in close proximity to the subject lands. As such, the redevelopment optimizes the use of existing municipal infrastructure.

Section 1.7 provides direction on the province’s long-term economic prosperity, and states:

“1.7.1 Long-term economic prosperity should be supported by:

b) encouraging residential uses to respond to dynamic market-based needs and provide necessary housing supply and range of housing options for a diverse workforce;

e) encouraging a sense of place, by promoting well-designed built form and cultural planning, and by conserving features that help define character, including built heritage resources and cultural heritage landscapes”

The proposed mixed-use buildings which front King Street East contribute to the Town’s supply of housing options and appropriately responds to market-based needs. The provision of these mixed-use spaces appropriately supports the province’s vision for long-term economic prosperity. Further, the retention of the former residential heritage farmhouse building and adaptive reuse of the barn structure into a future commercial community amenity area represents thoughtful integration of the Town’s rural heritage and cultural planning. Its location within separate blocks surrounded by a public open space allows the structures to serve as key focal points, encouraging a sense of place within the development.

Section 1.8 provides direction on energy conservation, air quality and climate change, and states:

“1.8.1 Planning authorities shall support energy conservation and efficiency, improved air quality, reduced greenhouse gas emissions, and preparing for the impacts of a changing climate through land use and development patterns which:

e) encourage transit-supportive development and intensification to improve the mix of employment and housing uses to shorten commute journeys and decrease transportation congestion”

The proposed development intensifies an area serviced by public transportation. The site’s close proximity to the Route 1 bus transit stop for Cobourg Transit optimizes investments in existing transit infrastructure, and supports the PPS’ direction for energy conservation, improved air quality and reduced greenhouse gas emissions through opportunities to shorten commute journeys and decrease transportation congestion. Further, the retained barn structure presents future opportunities for a commercial community amenity area.

Section 2 of the PPS provides direction on the protection of natural heritage, water, agricultural, mineral and cultural heritage and archaeological resources. Section 2.1.1 provides direction on the protection of natural features and areas, and states:

“2.1.1 Natural features and areas shall be protected for the long term.

2.1.2 The diversity and connectivity of natural features in an area, and the long-term ecological function and biodiversity of natural heritage systems, should be maintained, restored or, where possible, improved, recognizing linkages between and among natural heritage features and areas, surface water features and ground water features.

2.2.2 Development and site alteration shall be restricted in or near sensitive surface water features and sensitive ground water features such that these features and their related hydrologic functions will be protected, improved or restored.

Mitigative measures and/or alternative development approaches may be required in order to protect, improve or restore sensitive surface water features, sensitive ground water features, and their hydrologic functions.”

The proposed development provides for the protection and enhancement of the natural environment through the preservation of the wetland features in the north west portion of the site. A proposed Restoration Area with an approximately 15m buffer has been applied to the natural feature in accordance with the policies. The proposed Restoration Area is intended to be an environmental regeneration area which re-establishes environmental functions and offer intrinsic value to the community. A multi-use trail is proposed along the edge of the natural area to recognize the importance of linkages with the surrounding natural features in the area. Further, the subject site is adjacent to an Environmental Constraint Area to the east of the property.

The Environmental Impact Study by Pinchin Ltd. states that implementation of the environmental plans and proposed Restoration Area prior to and during construction of the site will preserve the ecological functions of the adjacent natural features.

Section 2.6 provides direction related to Cultural Heritage and Archaeology, and states:

“2.6.1 Significant built heritage resources and significant cultural heritage landscapes shall be conserved.

2.6.2 Planning authorities shall not permit development and site alteration on adjacent lands to protected heritage property except where the proposed development and site alteration has been evaluated and it has been demonstrated that the heritage attributes of the protected heritage property will be conserved.”

The proposed development contains a property listed on the Town of Cobourg Heritage Register of Properties of Cultural Heritage Value and Interest (Not Designated). The proposed development retains the former residential farmhouse building, barn structure and silos, and integrates them as a key focal point within the new community. The Heritage Impact Assessment (HIA) prepared by Martindale Planning dated April 5, 2022, provides an evaluation of the heritage resource and recommends the designation of 540 King Street East under Part IV of the Ontario Heritage Act. The HIA states that the proposed residential units will not overwhelm the retained heritage structures, and as such, the proposed development concept will not adversely impact the heritage significance of the property.

Given the above policies, the proposed Zoning By-law Amendment application required to implement the proposed development is consistent with the policies of the PPS.

6.2 The Growth Plan for the Greater Golden Horseshoe (2020)

The Growth Plan for the Greater Golden Horseshoe (2020), hereafter referred to as “the Growth Plan”, together with the Greenbelt Plan, Oak Ridges Moraine Conservation Plan, and the Niagara Escarpment Plan, builds on the Provincial Policy Statement (PPS) to provide a long-term land use planning framework for where and how the region and its municipalities will grow. The Growth Plan encourages the creation of complete community that supports economic prosperity, protects the environment, and helps achieve a high quality of life. The subject lands are located outside of the boundaries of the Greenbelt area, Oak Ridges Moraine Area, and Niagara Escarpment Plan area.

The Growth Plan states in Section 2.2.1.2:

“Forecasted growth to the horizon of this Plan will be allocated based on the following:

- a) the vast majority of growth will be directed to settlement areas that:

 - i. have a delineated built boundary;*
 - ii. have existing or planned municipal water and wastewater systems; and*
 - iii. can support the achievement of complete communities;**
- b) growth will be limited in settlement areas that:

 - i) are rural settlements;*
 - ii) are not serviced by existing or planned municipal water and wastewater systems; or*
 - iii) are in the Greenbelt Area;**
- c) within settlement areas, growth will be focused in:

 - i) delineated built-up areas;*
 - ii) strategic growth areas;*
 - iii) locations with existing or planned transit, with a priority on higher order transit where it exists or is planned; and*
 - iv) iv. areas with existing or planned public service facilities;**
- d) development will be directed to settlement areas, except where the policies of this Plan permit otherwise;*
- e) development will be generally directed away from hazardous lands; and*
- f) the establishment of new settlement areas is prohibited.”*

The Growth Plan directs that the majority of growth shall occur within settlement areas and particularly within delineated built-up areas. The subject lands are located within the Built Boundary of the Town’s Urban Settlement Area. The proposal is representative of a compact development that develops an underutilized parcel of land, making efficient use of existing services. The development of residential, mixed-use and community uses together assists in creating a complete community where residents can live, work and play in a transit-supportive neighbourhood.

Section 2.2.2 of the Growth Plan contains policies related to the delineated built up-areas and states:

“2.2.2.1 By the time the next municipal comprehensive review is approved and in effect, and for each year thereafter, the applicable minimum intensification target is as follows:

- b) The City of Kawartha Lakes and the Counties of Brant, Dufferin, Haldimand, Northumberland, Peterborough, Simcoe and Wellington will, through the next municipal comprehensive review, each establish the minimum percentage of all residential development occurring annually that will be within the delineated built-up area, based on maintaining or improving upon the minimum intensification target contained in the upper- or single-tier official plan.*

2.2.2.2. Until the next municipal comprehensive review is approved and in effect, the annual minimum intensification target contained in the applicable upper- or single-tier official plan that is approved and in effect as of July 1, 2017 will continue to apply.”

The proposed development is within the Town’s built boundary and will assist in achieving the intensification target as outlined in the County of Northumberland Official Plan.

Section 2.2.6 of the Growth Plan provides direction on housing and the creation of complete communities, and states:

“2.2.6.1 Upper- and single-tier municipalities, in consultation with lower-tier municipalities, the Province, and other appropriate stakeholders, will:

- a) support housing choice through the achievement of the minimum intensification and density targets in this Plan, as well as the other policies of this Plan by:

 - i. identifying a diverse range and mix of housing options and densities, including additional residential units and affordable housing to meet projected needs of current and future residents;**

2.2.6.3. To support the achievement of complete communities, municipalities will consider the use of available tools to require that multi-unit residential developments incorporate a mix of unit sizes to accommodate a diverse range of household sizes and incomes.

2.2.6.4. Municipalities will maintain at all times where development is to occur, land with servicing capacity sufficient to provide at least a three-year supply of residential units. This supply will include, and may exclusively consist of, lands suitably zoned for intensification and redevelopment.”

The proposed development intensifies an underutilized parcel of land, providing a diverse range and mix of housing options including single-detached, semi-detached, townhouses, stacked townhouses and mixed uses of various unit sizes which contribute to meeting the projected needs of current and future residents of the Town of Cobourg. Service capacity exists in the municipal infrastructure services to support the intensification of the subject property.

Section 3.2.2 of the Growth Plan contains policies related to Transportation, and states:

“3.2.2 In the design, refurbishment, or reconstruction of the existing and planned street network, a complete streets approach will be adopted that ensures the needs and safety of all road users are considered and appropriately accommodated.”

The proposed development establishes a new interior private street network which features a curved design and facilitates a pedestrian-friendly environment. Additionally, the new interior street network supports a complete streets approach by introducing design standards such as painted sharrows, planted boulevards and on-street parking to facilitate active transportation and traffic calming.

Section 3.2.7 of the Growth Plan contains policies related to Stormwater Management, and states:

“3.2.7.2 Proposals for large-scale development proceeding by way of a secondary plan, plan of subdivision, vacant land plan of condominium or site plan will be supported by a stormwater management plan or equivalent, that:

- a) is informed by a subwatershed plan or equivalent;*
- b) incorporates an integrated treatment approach to minimize stormwater flows and reliance on stormwater ponds, which includes appropriate low impact development and green infrastructure;*
- c) establishes planning, design, and construction practices to minimize vegetation removal, grading and soil compaction, sediment erosion, and impervious surfaces; and*

- d) *aligns with the stormwater management master plan or equivalent for the settlement area, where applicable.*”

The preliminary stormwater management plan by D.M. Wills was prepared to address impacts of the proposed development to existing drainage patterns. The report identified low impact development considerations and stormwater quality controls such as oil-grit separator structures as ways to mitigate increased stormwater flows. The report also identified underground chamber storage as stormwater quantity control measures and ensured that overall peak flows in catchments will be controlled.

Section 4.2.5 contains policies related to Public Open Space, and states:

“4.2.5.1 Municipalities, conservation authorities, non-governmental organizations, and other interested parties are encouraged to develop a system of publicly-accessible parkland, open space, and trails, including in shoreline areas, within the GGH that:

- a) clearly demarcates where public access is and is not permitted;*
- b) is based on a coordinated approach to trail planning and development; and*
- c) is based on good land stewardship practices for public and private lands.*

4.2.5.2 Municipalities are encouraged to establish an open space system within settlement areas, which may include opportunities for urban agriculture, rooftop gardens, communal courtyards, and public parks.”

The proposed development is located within the Urban Settlement Area and introduces several public open space areas throughout the development site. A Central Park marking the primary entrance to the new neighbourhood is proposed adjacent to the retained former residential farmhouse building and a parkette is proposed adjacent to the retained barn. Further, a restoration area is proposed at the west portion of the subject lands which contains a multi-use trail adjacent to the preserved and enhanced wetland natural feature. Together, these new parks and open spaces represent good land stewardship practices for private lands.

Section 4.2.7 contains policies related to Cultural Heritage Resources, and states:

“4.2.7.1 Cultural heritage resources will be conserved in order to foster a sense of place and benefit communities, particularly in strategic growth areas.”

The development proposes the retention of the listed heritage properties which include the former residential farmhouse, barn structure and associated silos. The residential farmhouse is proposed to be restored for residential use and the barn structure will be restored and adaptively reused as a commercial community amenity to locals, thereby fostering a sense of place and benefiting the larger community. The conservation and proposed adaptive reuse of the recognized heritage properties will help integrate the new development within the wider Town, as well as increase opportunities for the public to interact with these historic sites.

Based on the discussion above, it is our opinion that the proposed development is consistent with the applicable policies of the Growth Plan for the Greater Golden Horseshoe.

6.3 Northumberland County Official Plan (2016)

The Northumberland County Official Plan establishes land use categories and policies to manage growth and protect resources within the County until the year 2034. The County Official Plan primarily deals with issues of growth management and economic development and is intended to be consistent with the provincial planning framework. The purpose of the County Official Plan is to provide a basis for managing growth and change that support the County’s unique character, diversity, civic identity, urban and rural lifestyles, and natural and cultural heritage. The subject property is designated Urban Area (Schedule A) within the built boundary, and fronts onto King Street East which is identified as a County Arterial Road and County Cycling Network (Schedule C).

Cobourg is anticipated to see significant population growth based on the region's growth forecast. Section B2 states that a minimum of 80% of the expected population and employment in the planning period is expected to occur in the six Urban Areas, one being Cobourg. The regional growth forecast anticipates that Cobourg's Urban Area will absorb 48.4% of the regional share of the population growth to the year 2041.

Section C contains policies for the five land use designations within the regional Official Plan. The County encourages each of the six Urban Areas to become complete communities where there is a strong live/work ratio, a range of housing types, community and social services, cultural and recreational opportunities, and a population level and density that supports the provision of public transit. The proposed development meets these policy goals of building complete communities through the introduction of a mixed-use community which features a range of housing options, an adaptively reused cultural barn, and recreational opportunities within the new parks and open space areas. The proposed live-work spaces along the King Street East frontage further promotes the establishment of a complete community through offering places of residence and employment, while contributing to the Town's overall economic productivity.

Section C1.2 contains general land use objectives for Urban Areas. Within residential areas of the Urban Areas, the OP states the following general land use objectives:

"C1.2.1 It is the objective of this Plan to:

- a) Maintain and enhance the character and identity of existing residential areas;*
- b) Encourage the provision of a range of housing types to accommodate persons with diverse social and economic backgrounds, needs and desires while promoting the maintenance and improvement of existing housing;*
- c) Promote the efficient use of existing and planned infrastructure and public service facilities by supporting opportunities for various forms of residential intensification, where appropriate;*
- d) Encourage increases in density in new development areas to maximize the use of infrastructure and minimize the amount of land required for new development;*
- e) Promote a variety of complementary and compatible land uses in residential areas including special needs housing, community facilities, schools, small-scale commercial uses and recreational open space areas;*
- f) Encourage a high standard of urban design for development and redevelopment;*
- g) Encourage local municipalities to establish comprehensive design guidelines and policies to foster the establishment of communities that are safe, functional and attractive; and,*
- h) Implement street designs that provide for pedestrian, cycling and other non-motorized modes of transportation to help create more healthy and complete communities."*

The design of the proposed new neighbourhood demonstrates a compact form of development that is in keeping with the emerging patterns growth seen west of the site. Given the significant share of the region's population growth that Cobourg is anticipated to absorb in the next two decades, this form of residential intensification is appropriate for the subject lands. The retention and adaptive reuse of the heritage structures contribute to enhancing the town's existing rural identity. The diverse range of housing types contribute to the region's housing stock and the new development demonstrates optimized use of the existing infrastructure. Further, the proposed street network and built form represents a high standard of urban design that encourages active transportation. As such, the proposed development meets the objectives of the Official Plan with regard to residential areas within Urban Areas.

Section C1.2.4 of the County OP provides direction on the establishment of a system of public open spaces, parkland and recreational facilities that meets the needs of present and future residents. The OP encourages the development of a walking and cycling trail system within the open space system that is accessible to the public utilizing trails, paths, streets and other public open spaces. The proposed development introduces a restoration area to the west portion of the subject property with a multi-use trail and landscaped amenity area in the form of

a restoration area which encourages recreational activities and active transportation among present and future residents. Additional open spaces are woven throughout the site including the proposed Central Park and parkette adjacent to the retained heritage structures which complement the retained barn structure. These public amenities are proposed to integrate the area's natural heritage features such as hedgerows and wooded areas, thus meeting objectives of the Official Plan with regard to open space areas within Urban Areas.

Section C1.4 states that a full range of uses is permitted within Urban Areas in accordance with Local Official Plan policies and land use designations. Section C1.5 contains policies as they relate to Housing. The County encourages the provision of an appropriate range of housing types and densities, the achievement of residential intensification through encouraging mixed-use development opportunities, an appropriate range of housing types and densities. The policies of the OP states:

"C1.5.2 The County supports:

- a) Residential intensification and redevelopment within urban areas and rural settlement areas, where an appropriate level of infrastructure and public service facilities are or will be available in the immediate future and subject to the policies of this Plan"*

The proposed development appropriately meets the County's policy goals as they relate to regional housing needs through introducing a range of housing types within compact blocks in an area which is well-served with municipal infrastructure and public service facilities.

Section D3 contains policies as they relate to Cultural Heritage Resources. The County encourages the conservation of heritage buildings, cultural heritage landscapes and archaeological resources that are under municipal ownership and/or stewardship. The policies of the OP states:

"D3.5 Implementation

- a) Significant built heritage resources and significant cultural heritage landscapes shall be conserved.*
- c) The County will require a heritage impact assessment to be conducted by a qualified professional whenever a development has the potential to affect a cultural heritage resource, whether it is located on the same property or on adjacent lands.*
- d) A heritage impact assessment should outline the context of the proposal, any potential impacts the proposal may have on the heritage resource, and any mitigative measures required to avoid or lessen negative impact on the heritage resource.*
- g) Planning authorities shall not permit development and site alteration on adjacent lands to protected heritage property except where the proposed development and site alteration has been evaluated and it has been demonstrated that the heritage attributes of the protected heritage property will be conserved."*

The proposed development contains a significant built heritage resource that has been recognized by the Town of Cobourg as a Listed property on the Heritage Register of Properties of Cultural Heritage Value and Interest (Not Designated). The proposed development retains the former residential farmhouse building, barn structure and silos, and integrates them as a key focal point within the new community. The Heritage Impact Assessment (HIA) prepared by Martindale Planning provides an evaluation of the heritage resource and recommends the designation of 540 King Street East under Part IV of the Ontario Heritage Act. The HIA states that the proposed residential units will not overwhelm the retained heritage structures, and as such, the proposed development concept will not adversely impact the heritage significance of the property.

Section E contains general development policies that are to be considered with every application to develop land within the County through subdivision, condominium and consent to sever processes.

Section E2.2 contains policies as they relate to the Road Network. The subject property fronts onto King Street East, which is classified as a County Arterial Road. The OP states that County Arterial Roads connect urban areas and rural settlement areas and the Highway system. According to the general design guidelines, these roads can

have a right-of-way width up to 36.5 metres, discourage the use of private driveways, and have 2-4 travel lanes. The OP states:

“E2.2.2 Right-of-way Widths and Road Widening

b) The County may, without the need for an amendment to the Official Plan, require the dedication of lands to be used for daylight triangles, to provide sufficient sight distances and turning lanes to provide safe and appropriate access where major traffic generators intersect.

c) Where additional land is required for intersection improvements, such land shall be dedicated wherever possible, in the course of approving plans of subdivision or condominium, consents or site plan agreements, without amendment to this Plan.

d) As a condition of a development approval, land for road widenings shall be conveyed at no expense to the County or the local municipality in accordance with the provisions of the Planning Act. As a general principle, required road widenings will be taken equally from both sides of the right-of-way.

E2.2.3 County Road Design Standards

a) The County of Northumberland Public Works Department is responsible for County Roads located in the County. New development that requires access to or fronts on a County Road must satisfy all requirements of the Public Works and Planning Departments.

b) Development adjacent to or impacting on County Roads is subject to the County Roads Policies and entrance standards. In addition, setbacks from County Roads, unless stated elsewhere in a County By-law passed under the Municipal Act, will be in accordance with the Ministry of Transportation Corridor Control and Permit Procedures Manual.

E2.2.4 Pedestrian and Cycling Routes and Facilities

a) The County cycling network is shown on Schedule C to this Plan. Local municipalities in conjunction with the County are encouraged to develop interconnected systems of cycling and walking routes providing access to major activity and employment areas and to future public transit.

To accommodate future road widening at King Street East, a land conveyance has been accommodated for in the proposed development at the southern boundary.

Based on the above discussion, it is our opinion that the proposed development is in conformity to the County of Northumberland Official Plan. As such, an amendment to the Northumberland County Official Plan is not required to facilitate development of the subject property.

6.4 Town of Cobourg Official Plan (2018 Consolidation)

The Town of Cobourg Official Plan (“OP”) (2018 Consolidation) establishes a framework for the future planning of the community. The subject property is located within the Built Boundary and designated Residential Area, as per Schedule A – Land Use Plan (refer to Figure 4). The Residential Area land use designation provides for the creation of new residential areas which are generally compatible with the character and density of the existing residential areas. The permitted uses, buildings and structures in low density residential include single detached, semi-detached and duplex dwellings. For medium density residential it also includes townhouse dwellings, low-rise apartments and stacked townhouses.




Figure 4: Town of Cobourg Official Plan – Schedule A – Land Use Plan

The subject property is designated “Residential Area”, per Schedule A – Land Use Plan, which provides for the creation of new residential areas that are generally compatible with the character and density of the existing residential areas. Policy 3.4.3.2 outlines land use policies with regard to New Residential Areas. The OP states:

“3.4.3.2 In new residential areas or significant redevelopment areas, applications for development shall be evaluated based on their conformity with the Growth Management Strategy in Section 3.2 and all other applicable policies of this Plan and the following criteria:

- i) a mix of development forms and densities;*
- ii) medium density residential uses are encouraged and shall be:

 - a. intermixed with low density development in smaller groups;*
 - b. primarily street oriented in design; and,*
 - c. located adjacent to collector and arterial roads, park and Greenland areas, community facilities and commercial areas and/or as a physical transition between high and low density residential development.**
- iii) the road pattern is a modified, rectilinear grid pattern which provides for the maximum possible degree of connectivity internally, and externally with the existing developed areas and abutting arterial and collector roads with short blocks to promote active transportation modes; and,*
- iv) the development incorporates linkages to the Town’s greenland system and, incorporates private or public open space features or areas including Village Squares which serve as focal points for the residential development and/or structural elements which define the character and structure of the area.*

The proposed development is located on lands where medium density residential uses are encouraged. The proposal introduces a mix of development forms and densities with the addition of single detached, semi-detached, townhouse dwellings and stacked townhouses which are clustered in small groups throughout the site. The arrangement of the curved internal road system ensures connectivity not only within the site and with the abutting arterial road, but also provides opportunities for connection with a future development on the

abutting property through the east road extension. The proposed residential dwellings are street-oriented in design with their primary frontage addressing the adjacent streets and open spaces. Finally, the restoration area at the west portion of the site contributes a new landscaped amenity area within the residential community which incorporates linkages to the Town's natural greenland system.

Section 3.4.3.3 states that the density range for Medium Density residential development is as follows:

"3.4.3.3 ii) Medium Density

- a) 20 units per net hectare (8 units per net acre) minimum*
- b) 50 units per net hectare (20 units per net acre) maximum"*

The proposed development features a net density of 25.3 units per hectare (when calculated with a site area which subtracts the embankment and future road widening areas). Furthermore, the net density is 23.3 units per hectare (when calculated with a site area which subtracts the future road widening area only). Both density calculations meet the minimum density requirement for medium density residential development.

Section 3.4.3.4 states that the maximum height for residential development in New Residential Areas is four storeys. The proposed residential dwellings are within the OP's height limits.

Schedule A – Land Use Plan also identifies the subject property as adjacent to an Environmental Constraint Area located to the east. Section 4.2 Environmental Constraint Areas identifies policies related to development on and adjacent to these lands which are susceptible to flood or erosion. Specifically, Section 4.2.6 Environmental Impact Study or Environmental Audit: Lands Adjacent to Natural Heritage Features states:

"i) Lands Adjacent to Natural Heritage Features

Development and site alteration shall not be permitted on lands adjacent to the natural heritage features identified in Section 4.2.1 i) through ix), unless it has been demonstrated that there will be no negative impact on the natural features or their ecological functions through an Environmental Impact Study in accordance with terms of reference approved by the Town in consultation with the Conservation Authority and/or the Ministry of Natural Resources, or an environmental audit in accordance with Section 4.2.6 of this Plan. Adjacent lands shall be lands within 120 metres of those features listed in 4.2.1 i) through ix), with the exception of significant areas of natural and scientific interest-earth science where adjacent lands shall be within 50 metres of the feature.

ii) Environmental Audit

The environmental audit shall provide an inventory and analysis of all natural features and ecological functions on the site including vegetation, wildlife habitat, fish habitat, wetlands, steep slopes, habitat of endangered and threatened species, significant areas of natural and scientific interest, groundwater discharge areas and contribution to maintenance of fluvial processes. Particular regard shall be had for the relationship between the lands for which the environmental audit is being undertaken and the lands within the neighbouring Environmental Constraint Area. Where the environmental audit identifies significant natural environmental features and/or ecological systems, such areas shall be preserved and enhanced and consideration given to including them in the Environmental Constraint Area designation. In addition, submission of a detailed site plan, landscaping and grading plans will be required as the basis of the approval of any development, which shall demonstrate how natural ecological systems and processes will be maintained, including systems and processes in the Environmental Constraint Areas including addressing the issues of invasive species; and, -how disruption to existing landform and landscape features, including such features in the Environmental Constraint Area designation will be minimized.

Where no significant natural environmental features or ecological functions are identified, the development shall still be designed to maximize the protection of any features on the site and adjacent

Environmental Constraint Areas, but detailed plans and changes to the designation will not be required. Where the environmental audit indicates that there is an existing or potential hazard which cannot be overcome, or it is determined that the development cannot be designed in a manner which minimizes impact on the natural environment in an appropriate manner, there shall be no public obligation by the Town to permit development or purchase such lands. Where it is demonstrated that there are no natural features and ecological functions on the site including vegetation, wildlife habitat, fish habitat, wetlands, steep slopes, groundwater discharge areas and lands which contribute to maintenance of fluvial processes, the need for an environmental audit may be waived at the sole discretion of the Town, in consultation with the Conservation Authority.

An Environmental Impact Study prepared by Pinchin Ltd. demonstrates that the direct and indirect impacts of the proposed development can be avoided or mitigated through effective stormwater and environmental management measures. The Environmental Impact Study includes an assessment of existing conditions whereby an analysis of all natural features and ecological functions of the site are provided.

Section 4.5 contains policies as they relate to Tree Conservation and Planting. The OP prioritizes the preservation of natural vegetation that occurs in and adjacent to the Environmental Constraint Area. The subject property is adjacent to an Environmental Constraint Area per Schedule A – Land Use Plan. The following policies are applicable to the proposed development.

“4.5.2 Any person who has entered into an approved development agreement with the Town may remove trees in accordance with that agreement and the provisions of the Town’s Tree Preservation By-law. Where new development is to occur on a piece of land plan and an Arborist Report or similar report prepared by a qualified professional acceptable to the Town, shall be submitted and approved by the Town, either at the time of application or as a condition of approval at the direction of the Town. The Town shall consider the Tree Preservation Guidelines which form part of the Tree Preservation By-law in evaluating such plans and reports. In addition, such an analysis shall:

iii) address the impact of the development on any abutting lands in the Environmental Constraint Area designation, and the tree preservation, woodlot management and edge/interior protection measures required to protect such areas before, during and after the initiation of construction;”

A Tree Inventory and Preservation Plan Report was prepared by Pinchin Ltd. which inventoried relevant trees on and within 6m of the site. The report assesses impacts of development on existing trees and provides recommendations to protect trees identified for preservation within the wetland area.

Section 4.8 contains policies related to the Town’s Sustainability Strategy as it relates to development form. The OP states:

“4.8.2 In particular, the Town will encourage development designed to:

iii) create livable, healthy and productive environments.”

The proposed development represents a compact urban form which encourages active transportation and features a mix of uses including commercial uses along the King Street East frontage. The site’s intensification, retention of heritage resources and introduction of mixed uses contributes to creating a livable, healthy and productive environment.

Section 5 contains design policies related to Community Design and Improvement which help implement the Town’s principles related to community development such as “Distinctive Community Image”. The general design policies provide a framework for the review of development, alongside the Urban and Landscape Design Guidelines, for which the Town will also have regard when evaluating proposals for development. The policies of

Section 5 cover design policies as they relate to streetscapes, views, areas of heritage value/interest/significance, landscape design, safe community design, accessibility and visitability, active transportation, external building design, signage and mixed-use development.

The Urban, Landscape and Sustainability Study prepared by Fotenn Consultants identifies how the proposal satisfies the policies of Section 5 of the OP through evaluating the development against the One Planet Living Principles. These principles offer a framework for development that uses key performance indicators and targets to ensure environmental, social, cultural and economic sustainability. The Study states that the new development will seamlessly integrate into its surroundings, complementing and enhancing the area and the broader town while mitigating impacts on the community. A range of housing types located within compact blocks, surrounded by a well-connected network of streets and trails will encourage active living among its future residents. The proposed parks, public spaces and restoration area prioritizes and celebrates ecological functionality and sustainability.




Figure 5: Town of Cobourg Official Plan - Schedule E – Road Network Plan

Schedule E – Road Network Plan (Figure 5) identifies the subject property as located along an Existing Arterial and Existing and Planned Pedestrian/Bicycle Path along its King Street East frontage, and a Potential Pedestrian/Bicycle Path along its western property line. Section 6 of the Official Plan outlines policies related to the town’s Transportation Strategy. The following policies are relevant to the proposed development:

“6.2.2 Road Planning

ii) The Town, as a condition of development or redevelopment, may require lands for the purposes of road widening to be dedicated to the appropriate authority having jurisdiction in accordance with the requirements of Table 3. Additional lands in excess of the typical right-of-way widths may also be required to be conveyed for works related to, but not limited to, extensive cut/fill operations, intersection improvements, bridges, sight triangles, and drainage and buffering improvements.”

The Design Requirements within Table 3 of Section 6.2.2 state that roads classified as Arterials require a “maximum right-of-way width between 26-36 metres (86-118 feet), although generally will not exceed a maximum of 30 metres (98 feet)”. The portion of King Street East immediately south of the subject property does not meet the requirements for an Arterial road, and as such, the south portion of the site will be conveyed to the Town for the future right-of-way road widening.

As part of Cobourg’s Transportation Strategy, the Town promotes transit, cycling and other active transportation modes with the objective of establishing a transportation system that allows residents to safely travel anywhere within the town using active transportation modes. Policy 6.4 (iii) states:

“6.4 iii) The Town shall encourage the development of a link-node system which will connect major pedestrian and bicycle destinations such as schools, parks and commercial areas, the Main Central Area, the harbour, and the train station with a system of pedestrian and bicycle paths including sidewalks and on-street bicycle lanes where appropriate.

vi) The link-node system and other components of the transportation system shall be designed and developed to minimize conflicts between other modes of transportation and pedestrian and bicycle routes.

vii) Both in existing and future development, the transportation system shall be designed to provide for active transportation modes including the supportive infrastructure required for safe, convenient cycling and walking. In considering the design of active transportation modes, the Town shall take into consideration the following:

a) providing for bicycle lanes in the construction and reconstruction of streets and bridges;”

The proposed development features a curved internal street network and traffic calming design standards to facilitate a safe transportation network that encourages active transportation. On-street cycling infrastructure such as painted sharrows are incorporated on all streets within the community, contributing to the Town’s existing cycling network, and minimizing conflicts with other modes of transport. At the west portion of the subject property, a multi-use trail is proposed to be located adjacent to the restoration area at the west portion of the subject property, which builds on the Town’s existing natural linkages.

Section 6.5 contains policies related to Rail Safety. The OP states:

*“6.5.2 The Town shall review, as required, areas of conflict between the rail operations and pedestrian and vehicular movements, as well as conflicts with land uses abutting the rail lines including:
iii) the incorporation of safety measures such as the provision of security fencing for abutting land uses.”*

The proposed development incorporates a 30 metre buffer from the north property line which abuts the CN/CPR tracks to the building edge of the rear townhouses. An approximately 3 metre acoustical berm and 2 metre wall is located within this buffer area, providing appropriate separation distance from the residential uses. Additionally, the residential townhouses along the north portion of the site feature detached garages accessed from an adjacent laneway which are nestled into the acoustical berm, offering additional separation and safety from the railway.

Section 6.6 contains policies related to Parking within the Town. The OP states:

*“6.6.1 i) The Town shall require, as a condition of development or redevelopment, that:
a) adequate off-street vehicular parking and loading facilities be provided which are planned and engineered to allow access to all parking spaces;*

- b) ingress and egress to parking and loading areas be limited in number and designed to acceptable standards for traffic safety;”*

The proposed development incorporates three commercial visitor parking areas for the mixed-use buildings that front King Street East, and visitor parking areas for the retained barn structure, providing adequate vehicular parking facilities.

Section 7 contains policies related to the Town’s Municipal Infrastructure Strategy, which establishes the type and level of infrastructure that is required to support the existing and proposed land use pattern, as well as the staging of development. Policies related to Water Supply and Distribution System, Municipal Sewage Collection and Treatment System, and Existing Storm Water Facilities state:

“7.2.1 i) New development and/or redevelopment shall only be permitted where the water supply and distribution system has adequate capacity to service such development and/or redevelopment.

7.2.2 New Development

i) All new development shall be serviced by the municipal water supply and distribution system and the developer shall be responsible for the installation of such works subject to the approval of the Town, Lakefront Utilities Services Inc. and the Ministry of the Environment. The recommendations of any relevant watershed plan shall also be taken into consideration.

7.3.1 i) New development and/or redevelopment shall only be permitted where the sewage collection and treatment facilities are adequate to service such development.

7.3.2 New Development

i) All new development shall be serviced by the municipal sewage collection and treatment system and the developer shall be responsible for the installation of such works subject to the approval of the Town and the Ministry of the Environment. The recommendations of any relevant watershed plan shall also be taken into consideration.”

7.4.1 i) No development or redevelopment shall be permitted if such development or redevelopment will have a detrimental effect on the storm water drainage system.

iii) No development will be permitted which would interfere with or reduce the drainage capacity of any natural watercourse, and only those works may be carried out in the watercourses which will improve their hydraulic efficiency, their attractiveness as open space areas in accordance with the policies of Section 4 of this Plan and result in no net loss of fisheries habitat.

7.4.3 New Development

i) Stormwater management techniques and facilities for new development shall be selected and designed on a subwatershed basis in accordance with Provincial guidelines, particularly the Ministry of the Environment “Stormwater Management Planning and Design Manual 2003 or updates thereto, and in consultation with the Gananaska Region Conservation Authority. In particular stormwater management facilities shall be designed in a naturalized manner and will be landscaped so that they are integrated with the surrounding area and form part of the Greenlands System. The objectives of stormwater management with respect to new development within the Town of Cobourg shall be to:

- a) Identify appropriate water quality objectives for watercourse/drainage facilities to which the proposed developments are tributary with the primary focus being enhanced treatment;*
- b) identify and evaluate urban stormwater management practices to best meet these water quality objectives; and,*
- c) select appropriate stormwater management practices for the site and provide preliminary design, siting and sizing of proposed facilities.*

ii) With respect to stormwater quality control, development shall comply with the requirements of the approved Master Drainage Plan or stormwater plan. Where the Town requires the preparation of such plans they shall be prepared to the satisfaction of the Town at the expense of the applicant.

iii) Where new stormwater management facilities (i.e. detention/ retention ponds) are required to support development, they shall be located entirely within the boundaries of the Municipality.

iv) Notwithstanding the foregoing policies, the Town may provide for, in consultation with the Conservation Authority, intensification, redevelopment and/or extensions to residential areas which are substantially developed without storm sewer facilities provided that the proposed development is integrated with the present system in a manner which will not adversely affect adjacent properties and individual lot level approaches to reduce runoff volume and treat stormwater on site or other innovative approaches to stormwater management are used to the extent possible.

v) Individual lot level approaches are encouraged on all sites to reduce runoff volume and to treat stormwater on-site through Low Impact Development (LID) approaches including measures such as reduction of impervious areas, cisterns, porous or permeable pavement, green roofs, and bioswales.

7.4.4 Stormwater Management Studies

Stormwater management plans, master drainage plans, and other studies and works which involve the disposition of water, shall have regard for the maintenance of the natural ecological functions of the watercourses, waterbodies and surrounding lands which are subject to such works or studies."

The proposed development is located within the urban settlement area and represents the orderly development of an underutilized parcel of land which will be serviced by required municipal water, sewage and storm sewers. A Preliminary Stormwater Management report was prepared by D.M. Willis which recommended stormwater quality and quantity control measures to ensure that the receiving drainage system will not be adversely impacted. Appropriate low impact development approaches are outlined in the Stormwater Management report.

Section 7.5 contains policies related to Development Staging. Regarding Infilling and Intensification, the OP states:

"7.5.1 Development will be managed to efficiently use land, resources, infrastructure, and public service facilities and to avoid any unnecessary and/or uneconomic expansion of infrastructure. In particular, infilling and intensification are encouraged where lands are designated for the proposed use and full municipal services are available in accordance with the Growth Management Strategy in Section 3.2 and other relevant policies of this Plan."

The proposed development is located within Built Boundary of the town's Urban Settlement Area and therefore represents intensification in an area that has been designated for the proposed full use of municipal services.

Section 7.6 contains policies related to Utilities and Telecommunications. The OP states:

"7.6 i) All local power and telephone lines and other "cable" services serving new developed areas shall be located underground and shall be grouped into a single utility conduit, wherever possible. The Town shall also encourage all "cable" service providers in existing developed areas to locate their services underground whenever physically and financially possible."

The Functional Servicing Report prepared by D.M. Willis states that with regard to utilities, the Town's existing hydro provider LUSI has confirmed the existing overhead line in the King Street East ROW can service the proposed development. With regard to utilities, the report states that Bell has confirmed underground services are

available within the King Street East ROW. Further service details for utilities and telecommunications will be coordinated during the detailed design phase.

6.5 Zoning By-law 85-2003

The subject property is currently zoned Rural Exception 3 (RU-3) Zone – Rural Estate Lots for ‘Development Area C’ under the Town of Cobourg’s Zoning By-Law 85-2003 (refer to Figure 6).

The RU-3 Zone – Rural Estate Lots for ‘Development Area C’ permits a range of uses associated with rural and agricultural activities. The permitted buildings and structures within this zone are limited to those associated with agriculture use, park and golf course use, single-detached dwelling for group home use, and accessory buildings for permitted uses. A Zoning By-law Amendment will be required to implement the proposed development and is included as part of the submission materials.




Figure 6: Town of Cobourg Zoning By-Law 85-2003

Figure 6: Zoning

The proposed Zoning By-law Amendment seeks to rezone the subject lands from Rural Exception 3 Zone to R4, NMU, NR2, EC and OS Zone.

The following zoning table identifies the proposed development's compliance with the zone requirements within Section 5 - General Provisions.

General Provisions - Zone Requirement	Proposed	Compliance
<p>5.9 Requirement for Municipal Services Notwithstanding any other provisions of this By-law, no lands shall be used nor any building or structure erected or used thereon unless such municipal services as the Town ordinarily requires upon the development or redevelopment of land are available and capable of servicing the said land, building or structures.</p>	<p>The subject property is serviced by municipal sewage and stormwater services.</p>	<p>Yes</p>
<p>5.11 Lots to Front on Public Road 5.11.1 Unless otherwise specified by this By-law, no person shall erect a building or structure, and no person shall use any building or structure, unless the lot upon which the building or structure is situated, erected, or proposed to be erected abuts or fronts on an assumed public street which has a width of 18 metres (60 feet) or more and which is of satisfactory construction and maintenance to permit the reasonable and safe passage of motor vehicles travelling in two directions and which is maintained by the municipality on a year round basis.</p>	<p>The proposed mixed-use buildings (S, T and V) have frontage onto King Street East.</p> <p>For the purpose of the proposed development, the buildings on the interior of the subject lands have frontage on a private street through the common element private road.</p>	<p>No</p>
<p>5.11.2 Notwithstanding the requirements of Section 5.11.1, a building or structure may be situated or erected on a lot which: i) fronts on an assumed public street provided such building or structure is set to meet or exceed the established building line, recognizes any road widenings to the Town's satisfaction, and is in compliance with any other requirements of this By-law; or, ii) is within a registered plan of subdivision, in accordance with the provisions of a subdivision agreement in respect of such plan of subdivision, notwithstanding that the roads within such plan of subdivision have not been assumed and are not being maintained by the Municipality; or, iii) is within a registered plan of subdivision which has been approved, after the adoption of this By-law, with road allowances of greater than 15m (50 ft), but less than 20m (66 ft); or, iv) fronts on a right-of-way that has a minimum 10m (33 ft) width</p>	<p>A right-of-way road allowance dedication of 5m will be granted to the Town to meet the minimum road width requirements of an Arterial road.</p>	<p>Yes</p>
<p>5.12 Planned Width of Street Allowance No person shall erect any building or structure in any zone on the following streets or portions of streets unless such building or structure conforms to the following setback requirements and furthermore, in</p>	<p>A right-of-way road allowance dedication will be granted to the Town to meet the minimum road width requirements of an Arterial road.</p>	<p>Yes</p>

General Provisions - Zone Requirement	Proposed	Compliance
<p>determining any requirements of the Zoning By-law, the portion of the lot lying within the setback shall be deemed not to form part of the lot:</p> <p>King Street (Brook to Normar) Existing Street Width of 21+ m (70+ ft) Planned Width of Street Allowance 30m (100 ft) Minimum Setback Requirements from Centreline of Street of 15m (50 ft)</p>		
<p>6.1.1 Parking Provisions The owner of every building or structure erected or used for any purpose hereinafter set forth shall provide and maintain for the sole use of the owner, occupant or other persons entering upon or making use of the said premises from time to time, parking spaces and parking areas as follows:</p> <p>i) Residential</p> <p>Townhouse or Multiple Unit Dwelling: 1.5 spaces per dwelling unit Dwelling unit in a mixed use development: 1 space per dwelling unit, in addition to the requirements for the other uses in the development</p> <p>Other Residential Uses: 2 spaces per dwelling unit Home Occupations: 2 spaces per dwelling unit Detached, Semi-Detached: 2 spaces per dwelling unit</p> <p>Visitor parking for residential uses in the NR2 Zone: Notwithstanding the provisions of Section 6.1.5 of this By-law, required visitor parking of 0.25 spaces per unit shall be provided on-street. No on-site parking spaces are required.</p> <p>ii) Commercial</p> <p>Office: 1 space for every 33 m² (355 ft²) of gross floor area or portion thereof Studio use for a photographer, an artist or craftsman: 1 space for every 50m² (540 ft²) of gross floor area or portion thereof</p> <p>Uses with less than 20 parking spaces: At least 1 handicap space per establishment</p>	<p>The proposed development meets all required parking standards.</p> <p>Townhouse: 2 spaces per dwelling unit (one in garage and one on driveway)</p> <p>Other residential Uses: Single-detached and semi-detached - 2 spaces per dwelling unit (one in garage and one on driveway)</p> <p>NR2 visitor parking spaces on street (required 4.5 spaces): 5 provided</p> <p>Other Commercial Uses: Mixed-use barn area (required 13 spaces): 49 provided, 4 accessible parking provided</p>	<p>Yes</p>

General Provisions - Zone Requirement	Proposed	Compliance
<p>6.1.4 Dimensional Requirements</p> <p>i) Parking spaces shall have a minimum width of 2.7 m (9 ft) and a minimum depth of 5.5 m (18 ft).</p> <p>ii) Driving aisles providing access to parking spaces shall have a minimum width of 6 m (20 ft).</p> <p>iii) Notwithstanding the provisions of Section 6.1.4 i) handicap parking spaces shall have a minimum area of 24 m² (258 ft.²) and a minimum width of 4 m (13 ft).</p>	<p>Parking spaces meet the minimum dimensional requirements</p>	<p>Yes</p>
<p>6.1.5 Location</p> <p>i) Parking spaces shall be located on the same lot as the use they serve</p>	<p>The majority of buildings feature parking within the same lot as the use they serve. The parking for townhouses at the rear have detached garages accessed from a rear-lane. The commercial visitor parking for the mixed-use buildings are provided in surface parking lots. The barn cultural use and parkette feature nearby surface parking.</p>	<p>Yes</p>
<p>6.1.5.2 Notwithstanding any other provisions of this By-law, uncovered surface parking spaces shall be permitted in accordance with the following:</p> <p>i) Yards: Residential (other than apartments): Parking may be permitted in any yard provided that such parking is located within a driveway which is in accordance with the provisions of Section 6.1.6.2 and 6.1.6.3.</p>		<p>Yes</p>
<p>6.1.6.3 Driveway Regulations - General</p> <p>i) The minimum angle of intersection between a driveway and a street line shall be 60 degrees.</p> <p>ii) The minimum distance between two separate driveways on one lot, measured along the street line, shall be 9 m (30 ft.).</p> <p>iii) No driveway shall be closer than 1.0 m (3.3 ft.) to a side lot line, provided that this shall not apply to prevent the establishment of joint driveways along a common line.</p>		<p>Yes</p>

The following zoning table identifies the relief required for the proposed site-specific NR2 zone for buildings D, E, F, G, H, I, J, K, M, N, O, P, which encompass single-detached, semi-detached and townhouse buildings. In reaching the NR2 zone, an analysis of the proposed development against the R4 zone category was conducted to understand the best fit for buildings D, E, F, G, H, I, J, K, M, N, O, P. The zoning standard for the R4 zone as well as the proposed development’s compliance to this zone is shaded in grey below.

NR2 Zone Requirement	R4 Zone Requirement	Proposed	Compliance
<p>28.1.1 Permitted Uses</p> <ul style="list-style-type: none"> i) accessory use, including a garden suite use; ii) day nursery use; iii) group home use in accordance with the provisions of Section 5.2.2; iv) home occupation use; v) public use in accordance with the provisions of Section 5.3.2; vi) residential use. 	<p>10.1.1 Permitted Uses</p> <ul style="list-style-type: none"> i) Public use in accordance with the provisions of Section 5.3.2; ii) Residential use 	<p>The proposed uses for buildings D, E, F, G, H, I, J, K, M, N, O, P are residential use.</p>	<p>NR2: Yes R4: Yes</p>
<p>Appli28.1.2 Permitted Buildings and Structures</p> <ul style="list-style-type: none"> i) one single-detached dwelling on one lot; ii) one unit of a semi-detached dwelling on one lot; iii) one semi-detached dwelling on one lot; iv) one duplex dwelling on one lot; v) one converted dwelling on one lot with a maximum of two dwelling units; vi) one linked dwelling on one lot; vii) one triplex dwelling on one lot; viii) one fourplex dwelling on one lot; ix) one unit of a fourplex dwelling on one lot; x) one townhouse dwelling on one lot; xi) one townhouse dwelling unit on one lot; xii) buildings and structures for public uses in accordance with the provisions of Section 5.3.2; xiii) accessory buildings and structures for the permitted uses. 	<p>10.1.3 Permitted Buildings and Structures</p> <ul style="list-style-type: none"> i) one unit of a semi-detached dwelling on one lot; ii) one semi-detached dwelling on one lot; vii) townhouse dwelling including a townhouse dwelling for senior citizen’s and/or the disabled; viii) one multiple dwelling on one lot including a multiple dwelling for senior citizens and/or the disabled 	<p>Buildings D-P are proposed to be a combination of single-detached, semi-detached and townhouse buildings.</p>	<p>NR2: Yes R4: No</p>
<p>Minimum Lot Frontage (on a lot accessed by a lane)</p> <ul style="list-style-type: none"> - Single-detached: 8.0m - Single-detached (shallow-wide lots): N/A - Semi-detached: 6.6m/unit (7.8m if one semi is located on a corner lot, 14.4m if 2 semi units are located on a corner lot) - Townhouse: 5.5m/unit (6.7m for end unit on interior lot, 7.9m for end unit on a corner lot) 	<p>10.1.5: Lot Frontage</p> <ul style="list-style-type: none"> i) one unit of a semi-detached dwelling: 9m minimum ii) one semi-detached building on one lot: 18m minimum iv) townhouse dwelling which does not front onto a public street: 30m minimum 	<p>Lot not accessed by a lane: Single detached (F, I): 12m Townhouse: 6.0m/unit, 8.2m for end unit on interior lot, 7.9m for end unit on a corner lot</p>	<p>NR2: Yes R4: Yes</p>

<p>Minimum Lot Frontage (on a lot not accessed by a lane)</p> <ul style="list-style-type: none"> - Single-detached: 9.0m - Single-detached (shallow-wide lots): 13.3m - Semi-detached: 7.6m/unit (8.8m if one semi is located on a corner lot, 16.4m if 2 semi units are located on a corner lot) - Townhouse: 7.0m/unit (6.7m for end unit on interior lot, 7.9m for end unit on a corner lot) 	<p>v) townhouse dwelling where each townhouse unit fronts onto a public street: 6.5m per unit minimum</p>	<p>Single detached (G, H, J, K): 11.6m Semi-detached (unit): 8.8m Semi-detached (building): 19.2m Townhouse: N/A</p>	
<p>Minimum Required Front Yard (on a lot accessed by a lane)</p> <ul style="list-style-type: none"> - Single-detached: 3.0 m (at least 70% of the front wall of the main building shall be located within 1.5m of, or on, the building line. In no case shall the front wall be located in the minimum front yard) <p>Minimum Required Front Yard (on a lot not accessed by a lane)</p> <ul style="list-style-type: none"> - Single-detached: 4.5m (At least 70% of the front wall of the main building shall be located within 1.5 metres of, or on, the building line. In no case shall the front wall be located in the minimum required front yard) - Single-detached (shallow-wide lots): N/A - Semi-detached: 4.5m (At least 70% of the front wall of the main building shall be located within 1.5 metres of, or on, the building line. In no case shall the front wall be located in the minimum required front yard) - Townhouse: 4.5m (At least 70% of the front wall of the main building shall be located within 3.0 metres of, or on, the building line. In no case shall the front wall be located in the minimum required front yard) 	<p>10.1.9: Front Yard</p> <ul style="list-style-type: none"> - The established building line or where not applicable, 6m minimum. 	<p>Single detached (F, I): 4.5m</p> <p>Single Detached (G, H, J, K): 4.5m Semi-detached: 4.5m Townhouses (D, E): 4.5m</p>	<p>NR2: Yes</p> <p>R4: No – townhouse doesn't meet required front yard</p>

<p>Maximum driveway width on a lot not accessed by a lane (on lot with frontage less than 11.6m)</p> <ul style="list-style-type: none"> - Single-detached: 3.5m - Single-detached (shallow-wide lots): N/A - Semi-detached: The maximum driveway width and maximum garage width on a lot that has a lot frontage of 9.0 metres or less and which is not accessed by a lane is 3.5 metres. The maximum driveway width and maximum garage width on a lot that has a lot frontage of greater than 9.0 metres is 6.1 metres - Townhouse: same as above <p>(On lot with frontages greater than 11.6m):</p> <ul style="list-style-type: none"> - Single-detached: 6.1m - Single-detached (shallow-wide lots): 6.1m 	<p>N/A</p>	<p>For lot not accessed by a lane, frontage less than 11.6m:</p> <p>Single detached (G, J): 3.2m Semi-detached: 3.4m Townhouses: 3.0m</p> <p>On lot with frontage greater than 11.6m: Single detached (H, K): 3.2m</p>	<p>NR2: Yes</p>
<p>Maximum garage width on a lot that is not accessed by a lane (on a lot with a lot frontage of less than 11.6m)</p> <ul style="list-style-type: none"> - Single-detached: 3.5m - Single-detached (shallow-wide lots): N/A - Semi-detached: The maximum driveway width and maximum garage width on a lot that has a lot frontage of 9.0 metres or less and which is not accessed by a lane is 3.5 metres. The maximum driveway width and maximum garage width on a lot that has a lot frontage of greater than 9.0 metres is 6.1 metres) - Townhouse: same as above 	<p>N/A</p>	<p>Single-detached (G, J): 2.7m Semi-detached: 2.7m Townhouses: 2.7m</p>	<p>NR2: Yes</p>
<p>Minimum required exterior side yard</p> <ul style="list-style-type: none"> - Single-detached: 2.4m (The wall of an attached private garage that contains the opening for vehicular access shall be set back a minimum of 5.8 metres from the lot line that the driveway crosses to access the private attached garage. If the driveway does not cross a sidewalk, the minimum setback for the wall of the attached private garage that contains the opening for vehicular access is 4.5 m) - Single-detached (shallow-wide lots): same as above - Semi-detached: same as above - Townhouse: same as above 	<p>10.1.12: Exterior side yard</p> <ul style="list-style-type: none"> - The established building line, or where not applicable, 6m minimum. 	<p>Singles: no exterior sideyard Semi-detached: 4.3m Townhouses: 4.6 to private road</p>	<p>NR2: Yes</p> <p>R4: No</p>

<p>Minimum required interior side yard (on a lot with frontage less than 11.6m)</p> <ul style="list-style-type: none"> - Single-detached: 1.2m & 0.3m (The required interior side yard on one side is 2.75 metres if a detached private garage is located in the rear yard and is accessed by a driveway crossing the front lot line) - Single-detached (shallow-wide lots): N/A - Semi-detached: 1.2m & 0.0m (The required interior side yard on one side is 2.75 metres if a detached private garage is located in the rear yard and is accessed by a driveway crossing the front lot line) - Townhouse: 0.0m for interior unit & 1.2m for end unit <p>On lot with frontages greater than 11.6 (single detached lots) Single Detached 1.2m and 0.6m (The required interior side yard on one side is 2.75 metres if a detached private garage is located in the rear yard and is accessed by a driveway crossing the front lot line)</p>	<p>10.1.11: Interior Side Yard:</p> <p>i) One unit of a semi-detached dwelling, or a townhouse unit: no interior side yard shall be required between the common vertical wall dividing one dwelling unit from another. The side yard on the other side of the unit shall be 1.5m minimum and 1m for each additional storey</p> <p>ii) A duplex building; one semi-detached building on one lot; one converted, two unit building: 2.5m minimum for each interior side yard</p>	<p>Singles (G, J): 1.2m Semi-detached: 1.8m and 0.0m Townhouse: 1.8m and 0.0m</p> <p>Singles (F, H, I, K): 1.2m</p>	<p>NR2: Yes R4: No</p>
<p>Minimum required rear yard (on a lot accessed by a lane):</p> <ul style="list-style-type: none"> - Single-detached: 12.5m - Single-detached (shallow-wide lots): N/A - Semi-detached: 12.5m - Townhouse: 12.5m <p>Minimum required rear yard (on a lot not accessed by a lane):</p> <ul style="list-style-type: none"> - Single-detached: 7.5m - Single-detached (shallow-wide lots): 7.0m - Semi-detached: 7.5m - Townhouse: 7.5m 	<p>10.1.10: Rear yard</p> <ul style="list-style-type: none"> - 7m minimum 	<p>Singles (F, I): 11.4m Townhouse: 5.5m</p> <p>Single Detached (G, H, J, K): 7.5m Semi-detached: 7.5m</p>	<p>NR2: No R4: Yes</p>
<p>Maximum Height</p> <ul style="list-style-type: none"> - Single-detached: 11.0m - Single-detached (shallow-wide lots): 11.0m - Semi-detached: 11.0m - Townhouse: 11.0m 	<p>10.1.16: Building height</p> <ul style="list-style-type: none"> - 3 storeys maximum 		<p>NR2: Yes R4: No</p>

<p>Maximum lot coverage</p> <ul style="list-style-type: none"> - Single-detached: 50% - Single-detached (shallow-wide lots): 50% - Semi-detached: 50% - Townhouse: 50% 	<p>10.1.6: Lot coverage</p> <ul style="list-style-type: none"> - 40% maximum 	<p>Single detached: 32.8% Semi detached: 38.1% Townhouse: 47%</p>	<p>NR2: Yes R4: No</p>
<p>Driveway Setback</p> <ul style="list-style-type: none"> - Single-detached: 0m - Single-detached (shallow-wide lots): 0m - Semi-detached: 1m - Townhouse: 0m 	<p>N/A</p>	<p>Single detached: 1.2m Semi detached: 1.8m Townhouse: 0m</p>	<p>NR2: Yes</p>
<p>28.1.6: Regulations for accessory buildings and structures Parking garages/other accessory buildings and structures not attached to the main building shall not be located within 1m of a side/rear lot line except that:</p> <ol style="list-style-type: none"> a) On a corner lot where the minimum side yard abutting a street shall be 3m; b) Common semi-detached parking garages may be centred on a mutual side lot line; c) Where access to a parking garage is through a rear lot line, the garage may be located on the side lot line (zero lot line) and/or the rear lot line. 	<p>10.1.19: Regulations for accessory buildings and structures</p> <p>Private garages and other accessory buildings and structures not attached to the main building shall:</p> <ol style="list-style-type: none"> i) not be used for human habitation ii) not be built closer to the front lot line than the main building on the lot iii) have a minimum exterior side yard abutting the street line of 6m for a detached parking garage on a corner lot. For a detached accessory structure that is not intended for the storage or parking of a motor vehicle, boat storage, snowmobile, etc. and does not have an associated driveway, a minimum 1m exterior side yard may be permitted iv) have a minimum interior side yard of 1m. Semi-detached garages may be centred on a mutual side lot line v) have a minimum rear yard of 1m vi) not exceed 4.5m in height; vii) not exceed 8% coverage of the lot area, provided that the coverage of all buildings on the lot shall not exceed 40% of the lot area viii) not be located within 1.5m of any other building or structure on the lot 	<p>Setback for detached garages for single-detached houses (F, I): 0m setback to rear lot line</p>	<p>NR2: No R4: No</p>

The following zoning table identifies the relief required for the proposed site-specific R4 zone for buildings Q, R, and U. In reaching the R4 zone, an analysis of the proposed development against other zone categories was conducted to understand the best fit for buildings Q, R, U. The zoning standard for the NR2 zone as well as the proposed development's compliance to this zone is shaded in grey below.

R4 Zone Requirement	NR2 Zone Requirement	Proposed	Compliance
<p>10.1.1 Permitted Uses i) public use in accordance with the provisions of Section 5.3.2 ii) residential use</p>	<p>28.1.1 Permitted Uses i) accessory use, including a garden suite use; ii) day nursery use; iii) group home use in accordance with the provisions of Section 5.2.2; iv) home occupation use; v) public use in accordance with the provisions of Section 5.3.2; vi) residential use.</p>	<p>Proposed uses for buildings Q, R and U are residential uses.</p>	<p>R4: Yes NR2: Yes</p>
<p>10.1.3 Permitted buildings and structures i) one unit of a semi-detached building on one lot; ii) one semi-detached dwelling on one lot; vii) townhouse dwelling including a townhouse dwelling for senior citizens and/or the disabled; viii) one multiple dwelling on one lot including a multiple dwelling for senior citizens and/or the disabled; xii) accessory buildings and structures for the permitted uses.</p>	<p>28.1.2 Permitted Buildings and Structures i) one single-detached dwelling on one lot; ii) one unit of a semi-detached dwelling on one lot; iii) one semi-detached dwelling on one lot; iv) one duplex dwelling on one lot; v) one converted dwelling on one lot with a maximum of two dwelling units; vi) one linked dwelling on one lot; vii) one triplex dwelling on one lot; viii) one fourplex dwelling on one lot; ix) one unit of a fourplex dwelling on one lot; x) one townhouse dwelling on one lot; xi) one townhouse dwelling unit on one lot; xii) buildings and structures for public uses in accordance with the provisions of Section 5.3.2; xiii) accessory buildings and structures for the permitted uses.</p>	<p>Buildings Q, R and U are proposed to be stacked townhouse dwellings on three lots.</p>	<p>R4: Yes NR2: Yes – townhouses permitted</p>

<p>10.1.4 Lot Area</p> <p>iv) townhouse dwelling: 215m² minimum per dwelling unit</p>	<p>N/A</p>	<p>Building R has a minimum lot coverage of 205m² per 2 stacked dwelling units.</p>	<p>R4: No</p>												
<p>10.1.5 Lot Frontage</p> <p>iv) townhouse dwelling which does not front onto a public street: 30m minimum</p> <p>v) townhouse dwelling where each townhouse unit fronts onto a public street: 6.5m per unit minimum</p>	<p>Minimum Lot Frontage (on a lot accessed by a lane) - Townhouse: 5.5m/unit (6.7m for end unit on interior lot, 7.9m for end unit on a corner lot)</p> <p>Minimum Lot Frontage (on a lot not accessed by a lane) - Townhouse: 7.0m/unit (6.7m for end unit on interior lot, 7.9m for end unit on a corner lot)</p>	<p>The minimum lot frontage for an individual unit for buildings Q, R and U is 6.0m.</p> <p>Building Q has a frontage of 6.4 m. Building R has a frontage of 6.4m. Building U has a frontage of 38m.</p>	<p>R4: No – building Q/R does not meet minimum lot frontage</p> <p>NR2: No – minimum lot frontage for units not met</p>												
<p>10.1.6 Lot Coverage</p> <p>40% maximum</p>	<p>Maximum lot coverage - Townhouse: 50%</p>	<p>The lot coverage for buildings Q, R and U are 41, 51 and 47% respectively.</p>	<p>R4: No</p> <p>NR2: No</p>												
<p>10.1.7 Net Density - Apartment Dwelling/Converted Building/Multiple Dwelling</p> <p>50 units per net hectare (20 units per net acre)</p>	<p>N/A</p>	<p>The net density for the proposed development is 33.27 units/hectare.</p>	<p>R4: N/A</p>												
<p>10.1.8 Floor Area Per Dwelling Unit</p> <table border="1" data-bbox="205 841 701 1133"> <thead> <tr> <th>Type of Dwelling Unit</th> <th>Minimum Floor Area</th> </tr> </thead> <tbody> <tr> <td>Bachelor Unit</td> <td>28 m²</td> </tr> <tr> <td>One Bedroom Unit</td> <td>42 m²</td> </tr> <tr> <td>Two Bedroom Unit</td> <td>56 m²</td> </tr> <tr> <td>Three Bedroom Unit</td> <td>70 m²</td> </tr> <tr> <td>Each Additional Bedroom</td> <td>10 m²</td> </tr> </tbody> </table>	Type of Dwelling Unit	Minimum Floor Area	Bachelor Unit	28 m ²	One Bedroom Unit	42 m ²	Two Bedroom Unit	56 m ²	Three Bedroom Unit	70 m ²	Each Additional Bedroom	10 m ²	<p>N/A</p>	<p>The floor area per dwelling for all buildings exceeds the minimum per type of unit.</p>	<p>R4: Yes</p>
Type of Dwelling Unit	Minimum Floor Area														
Bachelor Unit	28 m ²														
One Bedroom Unit	42 m ²														
Two Bedroom Unit	56 m ²														
Three Bedroom Unit	70 m ²														
Each Additional Bedroom	10 m ²														
<p>10.1.9 Front Yard</p> <p>The established building line or where not applicable, 6m minimum.</p>	<p>Minimum Required Front Yard (on a lot accessed by a lane) - Townhouse: 0 m (at least 70% of the front wall of the main building shall be located within 3.0m of, or on, the building line. In no case shall the front wall be located in the minimum required front yard)</p> <p>Minimum Required Front Yard (on a lot not accessed by a lane)</p>	<p>The minimum front yard for buildings Q, R and U is 4.5m.</p>	<p>R4: No</p> <p>NR2: Yes</p>												

	- Townhouse: 4.5m (At least 70% of the front wall of the main building shall be located within 3.0 metres of, or on, the building line. In no case shall the front wall be located in the minimum required front yard)		
10.1.10 Rear Yard 7m minimum	Minimum required rear yard (on a lot accessed by a lane): - Townhouse: 12.5m Minimum required rear yard (on a lot not accessed by a lane): - Townhouse: 7.5m	The minimum rear yard for buildings Q and R is 7.5m. Building U does not feature individual rear yards, but a shared amenity area is provided in its place.	R4: No – no individual rear yard for building U NR2: No – minimum townhouse rear yard not met, no rear yard for building U
10.1.11 Interior Side Yard i) one unit of a semi-detached dwelling, or a townhouse unit: no interior side yard shall be required between the common vertical wall dividing one dwelling unit from another. The side yard on the other side of the unit shall be 1.5m minimum and 1m for each additional storey. iii) one triplex, an apartment building, a four-plex building, a multiple building, one converted building with more than two, residential units or a rooming and boarding house: 3.65m minimum	Minimum required interior side yard - Townhouse: 0.0m for interior unit & 1.2m for end unit	The interior side yard between buildings Q and R is 1.4m.	R4: No – minimum side yard at Q and R not met NR2: Yes
10.1.12 Exterior Side Yard The established building line, or where not applicable, 6m minimum.	Minimum required exterior side yard - Townhouse: 2.4m (the wall of the attached garage facing the public street shall not be located more than 3.0m closer to the front lot line than either the main entry feature or main front entrance of the dwelling unit)	The minimum exterior side yard for Q, R and U is 2.5m.	R4: No NR2: Yes
10.1.13 Distance between exterior walls of townhouse buildings	N/A	The distance between the walls of building Q and R is 3.0m	R4: No

<p>The minimum distance between the exterior walls of any two groups of townhouse dwellings on one lot shall be:</p> <p>i) where both ends of the group are one storey: 3m minimum</p> <p>ii) in all other circumstances: 5m minimum</p>			
<p>10.1.14 Distance between buildings – Apartments, Converted Buildings or Multiple Buildings</p> <p>The minimum distance between any two apartment buildings, converted buildings or multiple buildings located on one lot shall be a measurement equivalent to the average height of the two buildings; however, where neither external wall facing the other building contains the window of a habitable room, the distance may be reduced to one half the average height of the two buildings.</p>	N/A	The distance between the stacked townhouse buildings at Q and R is 3.0m.	R4: N/A
<p>10.1.15 Landscaped Open Space</p> <p>Minimum 35% of the lot</p>	N/A	The landscaped open space for U is 35%.	R4: Yes
<p>10.1.16 Building Height</p> <p>3 storeys maximum</p>	<p>Maximum height:</p> <p>- Townhouses: 11.0 m</p>	The stacked townhouses at Q, R, and U are 3 storeys tall.	<p>R4: Yes</p> <p>NR2: No</p>
<p>10.1.19 Regulations for Accessory Buildings and Structures</p> <p>Private garages and other accessory buildings and structures not attached to the main building shall:</p> <p>i) Not be used for human habitation;</p> <p>ii) Not be built closer to the front lot line than the main building on the lot;</p> <p>iii) Have a minimum exterior side yard abutting the street line of 6m for a detached parking garage on a corner lot. For a detached accessory structure that is not intended for the storage of parking of a motor vehicle, boat storage, snowmobile, etc. and does not have an associated driveway, a minimum 1m exterior side yard may be permitted.</p> <p>iv) Have a minimum interior side yard of 1m. Semi-detached garages may be centred on a mutual side lot line;</p> <p>v) Have a minimum rear yard of 1m;</p> <p>vi) Not exceed 4.5m in height;</p>	<p>28.1.6: Regulations for accessory buildings and structures</p> <p>Parking garages/other accessory buildings and structures not attached to the main building shall not be located within 1m of a side/rear lot line except that:</p> <p>a) On a corner lot where the minimum side yard abutting a street shall be 3m;</p> <p>b) Common semi-detached parking garages may be centred on a mutual side lot line;</p> <p>c) Where access to a parking garage is through a rear lot line, the garage may be located on the side lot line (zero lot line) and/or the rear lot line.</p>	<p>Detached garages for Building Q and R have a minimum interior side yard of 0.3m.</p> <p>The detached garages at building Q, R and U do not have a rear yard.</p> <p>The detached garages at building Q, R, and U have a minimum exterior side yard of 3m.</p> <p>Building Q has a garage coverage of 11%.</p> <p>Building R has a garage coverage of 16%.</p> <p>Building U has a garage coverage of 16%.</p>	<p>R4: No – exceeds lot coverage</p> <p>NR2: Yes</p>

vii) Not exceed 8% coverage of the lot area, provided that the coverage of all buildings on the lot shall not exceed 40% of the lot area;		Lot coverage for all buildings exceeds 40%.	
viii) Not be located within 1.5m of any other building or structure on the lot.			

The following zoning table identifies the relief required for the proposed site-specific R4 zone for buildings A, B, C.

R4 Zone Requirement	Proposed	Compliance										
10.1.1 Permitted Uses i) public use in accordance with the provisions of Section 5.3.2 ii) residential use	The proposed uses at buildings A, B, C are residential uses.	R4: Yes										
10.1.3 Permitted buildings and structures i) one unit of a semi-detached building on one lot; ii) one semi-detached dwelling on one lot; vii) townhouse dwelling including a townhouse dwelling for senior citizens and/or the disabled; viii) one multiple dwelling on one lot including a multiple dwelling for senior citizens and/or the disabled; xii) accessory buildings and structures for the permitted uses.	Buildings A, B, C are proposed to be townhouses.	R4: Yes										
10.1.4 Lot Area iv) townhouse dwelling: 215m ² minimum per dwelling unit	The lot area for building A is 853 m ² . The lot area for building B is 684 m ² . The lot area for building C is 830 m ² .	R4: Yes										
10.1.5 Lot Frontage iv) townhouse dwelling which does not front onto a public street: 30m minimum v) townhouse dwelling where each townhouse unit fronts onto a public street: 6.5m per unit minimum	The minimum lot frontage for individual townhouse units is 6.0 m. The lot frontage for the entire townhouse building is 38.4m.	R4: No										
10.1.6 Lot Coverage 40% maximum	The maximum lot coverage for building A is 41.5%. The maximum lot coverage for Building B is 43.9%. The maximum lot coverage for Building C is 42.7%.	R4: No										
10.1.8 Floor Area Per Dwelling Unit <table border="1" data-bbox="205 1284 846 1448"> <thead> <tr> <th>Type of Dwelling Unit</th> <th>Minimum Floor Area</th> </tr> </thead> <tbody> <tr> <td>Bachelor Unit</td> <td>28 m²</td> </tr> <tr> <td>One Bedroom Unit</td> <td>42 m²</td> </tr> <tr> <td>Two Bedroom Unit</td> <td>56 m²</td> </tr> <tr> <td>Three Bedroom Unit</td> <td>70 m²</td> </tr> </tbody> </table>	Type of Dwelling Unit	Minimum Floor Area	Bachelor Unit	28 m ²	One Bedroom Unit	42 m ²	Two Bedroom Unit	56 m ²	Three Bedroom Unit	70 m ²	The townhouse units for building A, B, C are 3-bedroom units and have a minimum floor area of 49.99 m ² .	R4: No
Type of Dwelling Unit	Minimum Floor Area											
Bachelor Unit	28 m ²											
One Bedroom Unit	42 m ²											
Two Bedroom Unit	56 m ²											
Three Bedroom Unit	70 m ²											

Each Additional Bedroom	10 m ²		
10.1.9 Front Yard The established building line or where not applicable, 6m minimum.		The minimum front yard for buildings A, B, C is 4.5m	R4: No
10.1.10 Rear Yard 7m minimum		The minimum rear yard for buildings A, B, C is 4.7m.	R4: No
10.1.11 Interior Side Yard i) one unit of a semi-detached dwelling, or a townhouse unit: no interior side yard shall be required between the common vertical wall dividing one dwelling unit from another. The side yard on the other side of the unit shall be 1.5m minimum and 1m for each additional storey.		The minimum interior side yard for buildings A, B, C is 1.5m.	R4: No
10.1.12 Exterior Side Yard The established building line, or where not applicable, 6m minimum.		There are no exterior side yards	R4: N/A
10.1.13 Distance between exterior walls of townhouse buildings The minimum distance between the exterior walls of any two groups of townhouse dwellings on one lot shall be: i) where both ends of the group are one storey: 3m minimum ii) in all other circumstances: 5m minimum		The distance between the exterior walls of the townhouse buildings is 3.0m.	R4: No
10.1.15 Landscaped Open Space Minimum 35% of the lot		The minimum landscaped open space for building A is 58.5% The minimum landscaped open space for building B is 56.1%. The minimum landscaped open space for building C is 57.3%.	R4: Yes
10.1.16 Building Height 3 storeys maximum		The building height for buildings A, B, C is 3 storeys.	R4: Yes
10.1.19 Regulations for Accessory Buildings and Structures Private garages and other accessory buildings and structures not attached to the main building shall: i) Not be used for human habitation; ii) Not be built closer to the front lot line than the main building on the lot; iii) Have a minimum exterior side yard abutting the street line of 6m for a detached parking garage on a corner lot. For a detached accessory structure that is not intended for the storage of parking of a motor vehicle, boat storage, snowmobile, etc. and does not have an associated driveway, a minimum 1m exterior side yard may be permitted. iv) Have a minimum interior side yard of 1m. Semi-detached garages may be centred on a mutual side lot line;		The detached garages for buildings A, B, C has a minimum interior side yard of 1.3m. The detached garages have a lot coverage of 12% of the lot area. The detached garages do not have rear yard.	R4: No

<ul style="list-style-type: none"> v) Have a minimum rear yard of 1m; vi) Not exceed 4.5m in height; vii) Not exceed 8% coverage of the lot area, provided that the coverage of all buildings on the lot shall not exceed 40% of the lot area; viii) Not be located within 1.5m of any other building or structure on the lot. 		
--	--	--

The following zoning table identifies the relief required for the proposed site-specific NMU zone for buildings S, T and V.

NMU Zone Requirement	Proposed	Compliance
<p>29.1.1 Permitted Uses</p> <ul style="list-style-type: none"> i) apartment use; ii) commercial education use; iii) convenience commercial use; iv) eating establishment use; v) financial institution use; vi) gallery use; vii) institutional use; viii) office use; ix) personal service use including a dry-cleaning distribution station, but not a dry cleaning establishment; x) private or commercial club use; xi) retirement home use; xii) residential use as a secondary use in a commercial building; xiii) specialty food use including a butcher, baked goods outlet and delicatessen; xiv) studio use; xv) uses permitted in the NR2 Zone. 	<p>Buildings S, T and V are proposed to be mixed uses containing ground floor commercial uses with residential above.</p>	<p>NMU: Yes</p>
<p>29.1.2 Permitted Buildings and Structures</p> <ul style="list-style-type: none"> i) the buildings and structures permitted in the NR2 Zone; ii) a mixed use building or structure incorporating some or all of the permitted uses; iii) a non-residential building or structure incorporating a permitted use or uses; and, iv) accessory buildings and structures for the permitted uses. 	<p>Buildings S, T, and V are proposed to be mixed-use buildings.</p>	<p>NMU: Yes</p>
<p>29.1.4 Non-Residential Use and Mixed Use Building Regulations</p> <p>Buildings and structures for mixed and non-residential uses in accordance with the provisions of Table Two.</p>	<p><i>See compliance with Retail/Mixed Use 1 provisions below</i></p>	

<p>29.1.7 Regulations for Accessory Buildings and Structures Parking garages and other accessory buildings and structures not attached to the main building, with the exception of garden suites which shall be subject to the regulations in Table 3, shall not:</p> <ul style="list-style-type: none"> i) be used for human habitation; ii) be built closer to the front lot line than the main building on the lot; iii) be located within 1 m. (3.3 ft.) of a side or rear lot line, except that: <ul style="list-style-type: none"> a) on a corner lot where the minimum side yard abutting a street shall be 3 m.(10 ft.); b) common semi-detached parking garages may be centred on a mutual side lot line; c) where access to a parking garage is through a rear lot line, the garage may be located on the side lot line (zero lot line) and/or the rear lot line. iv) exceed 4.5 m (15 ft.) in height; v) exceed 8% coverage of the lot area; and, vi) be located within 1.5 metres (5 ft.) of any other building or structure on the lot. 	<p>The garages for buildings S, T and V are attached to the main building.</p>	<p>NMU: N/A</p>
<p>Retail/Mixed Use 1 – Zone Provision</p>		
<p>Maximum Lot Area: 0.6 ha</p>	<p>Building S has a lot area of 0.826 ha. Building T has a lot area of 0.826 ha. Building V has a lot area of 0.986 ha.</p>	<p>NMU: No</p>
<p>Minimum lot frontage: 20m</p>	<p>Building S has a lot frontage of 34.2m Building T has a lot frontage of 34.2m. Building V has a lot frontage of 30.8m.</p>	<p>NMU: Yes</p>
<p>Minimum required front yard: 1.8m</p>	<p>Building S, T and V has a minimum front yard of 1.8m.</p>	<p>NMU: Yes</p>
<p>Maximum front yard: 2.4m</p>	<p>Building S, T and V has a maximum front yard of 2.8m.</p>	<p>NMU: No</p>
<p>Minimum required exterior side yard: 1.8m</p>	<p>Building S has a minimum exterior side yard of 3.0 m (Building V)</p>	<p>NMU: Yes</p>
<p>Minimum required interior side yard: 0.0 m (the required yard shall be 3m on any side of the lot that abuts a Residential or Open Space Zone and the yard shall be used for landscaped open space)</p>	<p>Building S, T and V do not directly abut a Residential or Open Space Zone.</p>	<p>N/A</p>
<p>Minimum required rear yard: 7.5m</p>	<p>Building S, T and V do not have rear yards.</p> <p>A provision for a 30m² private amenity should be provided for each unit through balcony or rooftop.</p>	<p>NMU: No</p>
<p>Maximum lot coverage: 40%</p>	<p>Building S has a lot coverage of 71.7%. Building T has a lot coverage of 71.7%. Building V has a lot coverage of 67.7%.</p>	<p>NMU: No</p>
<p>Minimum landscaped open space: 20%</p>	<p>Building S has a landscaped open space of 25.4%. Building T has a landscaped open space of 25.4%.</p>	<p>NMU: Yes</p>

	Building V has a landscaped open space of 29.8%.	
Floor Space Index (FSI): N/A	N/A	N/A
Minimum height: N/A	N/A	N/A
Maximum height: 12.0m	Building S, T, V has a maximum building height of 11 m.	NMU: Yes

The following zoning table identifies the relief required for the proposed site-specific NMU zone for the retained barn area.

NMU Zone Requirement	Proposed	Compliance
<p>29.1.1 Permitted Uses</p> <ul style="list-style-type: none"> i) apartment use; ii) commercial education use; iii) convenience commercial use; iv) eating establishment use; v) financial institution use; vi) gallery use; vii) institutional use; viii) office use; ix) personal service use including a dry-cleaning distribution station, but not a dry cleaning establishment; x) private or commercial club use; xi) retirement home use; xii) residential use as a secondary use in a commercial building; xiii) specialty food use including a butcher, baked goods outlet and delicatessen; xiv) studio use; xv) uses permitted in the NR2 Zone. 	The retained barn structure may be used as a commercial/community amenity area with potential community uses including a coffeeshop, gathering area, studio space, public assembly, recreation or cultural use.	NMU: No
<p>29.1.2 Permitted Buildings and Structures</p> <ul style="list-style-type: none"> i) the buildings and structures permitted in the NR2 Zone; ii) a mixed use building or structure incorporating some or all of the permitted uses; iii) a non-residential building or structure incorporating a permitted use or uses; and, iv) accessory buildings and structures for the permitted uses. 	The retained barn is proposed to be a non-residential building which incorporates some of the permitted uses of the NR2 zone.	NMU: Yes
29.1.4 Non-Residential Use and Mixed Use Building Regulations Buildings and structures for mixed and non-residential uses in accordance with the provisions of Table Two.	<i>See compliance with Retail/Mixed Use 1 provisions below</i>	
29.1.7 Regulations for Accessory Buildings and Structures Parking garages and other accessory buildings and structures not attached to the main building, with the exception of garden suites which shall be subject to the regulations in Table 3, shall not:	The retained barn does not contain any accessory buildings.	N/A

<p>i) be used for human habitation; ii) be built closer to the front lot line than the main building on the lot; iii) be located within 1 m. (3.3 ft.) of a side or rear lot line, except that: a) on a corner lot where the minimum side yard abutting a street shall be 3 m.(10 ft.); b) common semi-detached parking garages may be centred on a mutual side lot line; c) where access to a parking garage is through a rear lot line, the garage may be located on the side lot line (zero lot line) and/or the rear lot line. iv) exceed 4.5 m (15 ft.) in height; v) exceed 8% coverage of the lot area; and, vi) be located within 1.5 metres (5 ft.) of any other building or structure on the lot.</p>		
Retail/Mixed Use 1 – Zone Provision		
Maximum Lot Area: 0.6 ha	The lot area for the commercial community barn is 0.2494 ha, inclusive of barn visitor parking.	NMU: Yes
Minimum lot frontage: 20m	Minimum lot frontage is 17.5m.	NMU: No
Minimum required front yard: 1.8m	Minimum front yard is 5.3m. This dimension excludes the existing silo structures located in front of the barn.	NMU: Yes
Maximum front yard: 2.4m	Maximum front yard is 6.1m.	NMU: No
Minimum required exterior side yard: 1.8m	Minimum exterior side yard (to block line) is 2.6m.	NMU: Yes
Minimum required interior side yard: 0.0 m (the required yard shall be 3m on any side of the lot that abuts a Residential or Open Space Zone and the yard shall be used for landscaped open space)	N/A	N/A
Minimum required rear yard: 7.5m	The commercial community barn features a parkette.	NMU: Yes
Maximum lot coverage: 40%	The commercial community barn has a lot coverage of 17.5%.	NMU: Yes
Minimum landscaped open space: 20%	The landscaped area for the commercial community barn is 47.7%.	NMU: Yes
Floor Space Index (FSI): N/A	N/A	N/A
Minimum height: N/A	N/A	N/A
Maximum height: 12.0m	Height of the commercial community hub is 10.18m.	NMU: Yes

The following zoning table identifies the relief required for the proposed site-specific NR2 zone for the retained residential farmhouse.

NR2 Zone Requirement	Proposed	Compliance
<p>28.1.1 Permitted Uses</p> <ul style="list-style-type: none"> i) accessory use, including a garden suite use; ii) day nursery use; iii) group home use in accordance with the provisions of Section 5.2.2; iv) home occupation use; v) public use in accordance with the provisions of Section 5.3.2; vi) residential use. 	<p>The retained residential farmhouse will contain residential uses.</p>	<p>NR2: Yes</p>
<p>28.1.2 Permitted Buildings and Structures</p> <ul style="list-style-type: none"> i) one single-detached dwelling on one lot; ii) one unit of a semi-detached dwelling on one lot; iii) one semi-detached dwelling on one lot; iv) one duplex dwelling on one lot; v) one converted dwelling on one lot with a maximum of two dwelling units; vi) one linked dwelling on one lot; vii) one triplex dwelling on one lot; viii) one fourplex dwelling on one lot; ix) one unit of a fourplex dwelling on one lot; x) one townhouse dwelling on one lot; xi) one townhouse dwelling unit on one lot; xii) buildings and structures for public uses in accordance with the provisions of Section 5.3.2; xiii) accessory buildings and structures for the permitted uses. 	<p>The retained residential farmhouse is a single-detached dwelling.</p>	<p>NR2: Yes</p>
<p>Minimum Lot Frontage (on a lot not accessed by a lane)</p> <ul style="list-style-type: none"> - Single-detached: 9.0m 	<p>The lot frontage for the retained residential farmhouse is 34.1m.</p> <p>The lot frontage is measured from the front lot line, which shall be the side that intersects the driveway.</p>	<p>NR2: Yes</p>
<p>Minimum Required Front Yard (on a lot not accessed by a lane)</p> <ul style="list-style-type: none"> - Single-detached: 4.5m (At least 70% of the front wall of the main building shall be located within 1.5 metres of, or on, the building line. In no case shall the front wall be located in the minimum required front yard) 	<p>The front yard for the retained residential farmhouse is 4.3 m.</p> <p>The front yard is measured from the front lot line, which shall be the side that intersects the driveway.</p>	<p>NR2: Yes</p>

<p>Maximum driveway width on a lot not accessed by a lane (On lot with frontages greater than 11.6m):</p> <ul style="list-style-type: none"> - Single-detached: 6.1m - Single-detached (shallow-wide lots): 6.1m 	The driveway width leading to the detached garage is 6.1m.	NR2: Yes
<p>Maximum garage width on a lot that is not accessed by a lane (on a lot with a lot frontage of less than 11.6m)</p> <ul style="list-style-type: none"> - Single-detached: 3.5m - Single-detached (shallow-wide lots): N/A 	The width of the detached garage is 6.1m.	NR2: Yes
<p>Minimum required exterior side yard</p> <ul style="list-style-type: none"> - Single-detached: 2.4m (The wall of an attached private garage that contains the opening for vehicular access shall be set back a minimum of 5.8 metres from the lot line that the driveway crosses to access the private attached garage. If the driveway does not cross a sidewalk, the minimum setback for the wall of the attached private garage that contains the opening for vehicular access is 4.5 m) - Single-detached (shallow-wide lots): same as above 	The retained residential farmhouse has a minimum exterior side yard of 3.8m.	NR2: Yes
<p>Minimum required interior side yard (On lot with frontages greater than 11.6m)</p> <ul style="list-style-type: none"> - Single Detached 1.2m and 0.6m (The required interior side yard on one side is 2.75 metres if a detached private garage is located in the rear yard and is accessed by a driveway crossing the front lot line) 	The interior side yard is 3 m.	NR2: Yes
<p>Minimum required rear yard (on a lot not accessed by a lane):</p> <ul style="list-style-type: none"> - Single-detached: 7.5m - Single-detached (shallow-wide lots): 7.0m 	The retained residential farmhouse has a rear yard 2.8m.	NR2: No
<p>Maximum Height</p> <ul style="list-style-type: none"> - Single-detached: 11.0m - Single-detached (shallow-wide lots): 11.0m - Semi-detached: 11.0m - Townhouse: 11.0m 	Height of the residential dwelling is 10.69m.	NR2: Yes
<p>Maximum lot coverage</p> <ul style="list-style-type: none"> - Single-detached: 50% - Single-detached (shallow-wide lots): 50% 	The lot coverage of the retained residential farmhouse is 22%	NR2: Yes

<p>Driveway Setback</p> <ul style="list-style-type: none"> - Single-detached: 0m - Single-detached (shallow-wide lots): 0m 	<p>There is no driveway setback from the front property line.</p>	<p>NR2: Yes</p>
<p>28.1.6: Regulations for accessory buildings and structures Parking garages/other accessory buildings and structures not attached to the main building shall not be</p> <p>ii) be built closer to the front lot line than the main building on the lot;</p> <p>iii) located within 1m of a side/rear lot line except that:</p> <ul style="list-style-type: none"> a) On a corner lot where the minimum side yard abutting a street shall be 3m; b) Common semi-detached parking garages may be centred on a mutual side lot line; c) Where access to a parking garage is through a rear lot line, the garage may be located on the side lot line (zero lot line) and/or the rear lot line. <p>iv) exceed 4.5m in height;</p> <p>v) exceed 8% coverage of the lot area; and</p> <p>vi) be located within 1.5m of any other building or structures on the lot.</p>	<p>The detached garage is built closer to the front lot line than the main building on the lot.</p>	<p>NR2: Yes</p>

7.0 APPENDICES

APPENDIX A: DRAFT ZONING BY-LAW AMENDMENT

The Corporation of the Town of Cobourg

By-law Number XXXX-2021

A BY-LAW TO AMEND ZONING BY-LAW NUMBER 85-2003 (Subject Lands municipally known as 540 King Street East, Cobourg)

WHEREAS the Municipal Council of the Corporation of the Town of Cobourg convened a Public Meeting in accordance with the Planning Act, R.S.O 1990, c.P.12, as amendment, on **DATE** regarding an application by **APPLICANT** to approve a Zoning By-Law Amendment for lands municipally known as 540 King Street East.

AND WHEREAS the Council of the Corporation of the Town of Cobourg duly considered all public submissions, the applicant's background information, the Manager of Planning's report and all other relevant background information surrounding the subject matter, and deems it advisable to approve an amendment to Comprehensive Zoning By-Law No.85-2003;

NOW THEREFORE the Municipal Council of the Corporation of the Town of Cobourg enacts as follows:

1. That Schedule 'A' attached to and forming part of By-law No.85-2003, is hereby amended by changing the zone category of the lands as illustrated on Schedule "B" attached hereto from Rural Exception 3 (RU-3) Zone – Rural Estate Lots for 'Development Area C' to Residential 4 Exception Zone (R4-xx), Neighbourhood Mixed Use Exception Zone (NMU-xx), Neighbourhood Residential Exception Zone (NR2-xx), Environmental Constraint Zone (EC) and Open Space Zone (OS).

2. That By-law 85-2003, Section 10.2 is hereby amended by the addition of the following subsections:

Add definition:

Exterior Side Yard shall mean a side yard immediately adjoining a public street, or private road, excluding a lane.

Stacked Townhouse shall mean a townhouse with demising walls which separate dwelling units vertically and horizontally.

3. That By-law 85-2003, Section 28.2 is hereby amended by the addition of the following subsections:

28.2.X Neighborhood Residential 2 Exception X (NR2-X) – Lands within 540 King Street East

28.2.X.1 Defined Area

NR2-X as shown on Map 5, portion of Schedule A to this By-law

28.2.X.2 Permitted Uses and Permitted Accessory Uses

The uses permitted shall be in accordance with Section 28.1.1

28.2.X.3 Permitted Buildings and Structures

The permitted buildings and structures shall be in accordance with Section 28.1.2

28.2.X.4 Regulations for Permitted Uses in the NR2-X Zone

The regulations of Section 28.1 shall apply to the permitted uses in the NR2-X Zone, with the exception of the following:

Lot Frontage

- i) For the purpose of the NR2-X zone, the front lot line shall be the lot line which contains the main front feature.

Rear Yard

- i) Single detached dwelling: 11.4m for lot accessed by a lane
- ii) Townhouses: 5.5m

Regulations for Accessory Buildings and Structures Detached parking garages shall not require a minimum setback from the rear lot line

28.2.X Neighborhood Residential 2 Exception X (NR2-X) – Lands within 540 King Street East

28.2.X.1 Defined Area

NR2-X as shown on Map 5, portion of Schedule A to this By-law

28.2.X.2 Permitted Uses and Permitted Accessory Uses

The uses permitted shall be in accordance with Section 28.1.1

28.2.X.3 Permitted Buildings and Structures

The permitted buildings and structures shall be in accordance with Section 28.1.2

28.2.X.4 Regulations for Permitted Uses in the NR2-X Zone

The regulations of Section 28.1 shall apply to the permitted uses in the NR2-X Zone, with the exception of the following:

Rear Yard

Single-Detached	For the purpose of the NR2-X zone, the front lot line is identified as the side that intersects with the driveway. Minimum rear yard shall be 2.8m
-----------------	--

Regulations for Accessory Buildings and Structures

Private garages and other accessory buildings and structures not attached to the main building shall: Notwithstanding 28.1.6 ii), the detached parking garage shall be set back 2.6m from the front lot line

4. That By-law 85-2003, Section 10.2 is hereby amended by the addition of the following subsections:

10.2.X R4 Multiple Residential 4 Exception X (R4-X) – Lands within 540 King Street East

10.2.X.1 Defined Area

R4-X as shown on Map 5, portion of Schedule A to this By-law

10.2.X.2 Permitted Uses and Permitted Accessory Uses

The uses permitted shall be in accordance with Section 10.1.1 and 10.1.2

10.2.X.3 Permitted Buildings and Structures

The permitted buildings and structures shall be in accordance with Section 10.1.3

10.2.X.4 Regulations for Permitted Uses in the R4-X Zone

The regulations of Section 10.1 shall apply to the permitted uses in the R4-X Zone, with the exception of the following:

Lot Area	Minimum lot area for a townhouse dwelling shall be 205m ² per 2 stacked dwelling units
Lot Frontage	Minimum lot frontage for a townhouse dwelling accessed from a rear lane shall be 6 m
Lot Coverage	Maximum lot coverage shall be 48%
Front Yard	Minimum front yard shall be 4.5m
Rear Yard	For buildings that do not have individual rear yard amenities, they shall have a common outdoor amenity area of 19m ² area (minimum).
Interior Side Yard	Minimum interior side yard shall be 1.5m total.
Exterior Side Yard	Notwithstanding 10.1.12 Exterior Sideyard Setback, Townhouse buildings shall not be located within 2.5m of a private road. Accessory structures from the wall of the building to the lot line shall have a 0m exterior sideyard setback.
Distance Between Buildings	Minimum distance between any two Townhouse buildings located on one lot shall be 3.0m.
Regulations for Accessory Buildings and Structures	Private garages and other accessory buildings and structures not attached to the main building shall: Notwithstanding 10.1.19 iii), detached garages shall have a minimum exterior sideyard of 3.0m. Notwithstanding 10.1.19 iv), detached garages shall have an interior side yard of 0.3m. Notwithstanding 10.1.19 vii), detached garages shall not exceed 16% of the lot area, provided that the coverage of all buildings on the lot shall not exceed 48% of the lot area.

10.2.X R4 Multiple Residential 4 Exception X (R4-X) – Lands within 540 King Street East

10.2.X.1 Defined Area

R4-X as shown on Map 5, portion of Schedule A to this By-law

10.2.X.2 Permitted Uses and Permitted Accessory Uses

The uses permitted shall be in accordance with Section 10.1.1 and 10.1.2

10.2.X.3 Permitted Buildings and Structures

The permitted buildings and structures shall be in accordance with Section 10.1.3

10.2.X.4 Regulations for Permitted Uses in the R4-X Zone

The regulations of Section 10.1 shall apply to the permitted uses in the R4-X Zone, with the exception of the following:

Lot Frontage	v) townhouse dwelling where each unit fronts onto a public street: For the purpose of the R4-X zone, townhouses shall have their frontage determined by the portion which contains the main entrance. The private road shall be considered a public street. Each townhouse dwelling unit shall have a minimum lot frontage of 6.0m
Lot Coverage	Maximum lot coverage shall be 44%
Floor Area per Dwelling Unit	Minimum Floor Area for Three-Bedroom Units shall be 50 m ²
Front Yard	Minimum front yard shall be 4.5m
Rear Yard	Minimum rear yard shall be 4.7 m
Interior Side Yard	i) one unit of a semi-detached dwelling, or a townhouse unit: No interior sideyard shall be required between the common vertical wall dividing one dwelling unit from another. The sideyard on the other side of the unit shall be 1.5m minimum in total.
Distance between Exterior Walls of Townhouses	Minimum distance between the exterior walls of any two groups of townhouse dwellings on one lot shall be 3.0m minimum in total
Regulations for Accessory Buildings and Structures	For the purpose of the R4-X zone, the townhouse buildings and their respective detached garages are considered to be located on a single lot. Notwithstanding 10.1.19 v), detached garages shall have no minimum rear yard. Notwithstanding 10.1.19 vii), detached garages shall not exceed 12% of the lot area, provided that the coverage of all buildings on the lot shall not exceed 44% of the lot area.

5. That By-law 85-2003, Section 29.2 is hereby amended by the addition of the following subsections:

29.2.X Neighbourhood Mixed Use (NMU-X) Regulations – Lands within 540 King Street East

29.2.X.1 Defined Area

NMU-X as shown on Map 5, portion of Schedule A to this By-law

29.2.X.2 Permitted Uses and Permitted Accessory Uses

The uses permitted shall be in accordance with Section 29.1.1 in addition to the following:

- Retail Commercial Use
- Fresh fruit, vegetable and flower sales use
- Market Use

29.2.X.3 Permitted Buildings and Structures

The permitted buildings and structures shall be in accordance with Section 29.1.2

29.2.X.4 Regulations for Permitted Uses in the NMU-X Zone

The regulations of Section 29.1.2 shall apply to the permitted uses in the NMU-X Zone, with the exception of the following:

Lot Area	Maximum lot area shall be 1 ha
Front Yard	Maximum Front Yard shall be 2.8m
Rear Yard	Townhouses that do not have rear yards shall have a private amenity area of 30m ² provided through a balcony or rooftop area. The attached garage shall be set back 1m from the private lane
Lot Coverage	Maximum lot coverage shall be 72%

29.2.X Neighbourhood Mixed Use (NMU-X) Regulations – Lands within 540 King Street East

29.2.X.1 Defined Area

NMU-X as shown on Map 5, portion of Schedule A to this By-law

29.2.X.2 Permitted Uses and Permitted Accessory Uses

The uses permitted shall be in accordance with Section 29.1.1 in addition to the following:

- Retail Commercial Use
- Market Use
- Public Place of Assembly Use
- Recreation and Community Centre Use
- Cultural Use

29.2.X.3 Permitted Buildings and Structures

The permitted buildings and structures shall be in accordance with Section 29.1.2

29.2.X.4 Regulations for Permitted Uses in the NMU-X Zone

The regulations of Section 29.1.2 shall apply to the permitted uses in the NMU-X Zone, with the exception of the following:

Lot Frontage

Minimum lot frontage shall be 17.5m

Front Yard

For the purpose of the NMU-X zone, the front yard calculation excludes the silos. Maximum front yard shall be 6.1m

Schedule 'B'




Areas to be rezoned from Rural Exception 3 (RU-3) Zone – Rural Estate Lots for ‘Development Area C’ to Residential 4 Exception Zone (R4-xx), Neighbourhood Mixed Use Exception Zone (NMU-xx), Neighbourhood Residential Exception Zone (NR2-xx), Environmental Constraint Zone (EC) and Open Space Zone (OS).

APPENDIX B: DRAFT PLAN OF SUBDIVISION

REVISIONS		
DRAWING NO.	DATE	DESCRIPTION
A	MAR 20, 2022	NEW DRAFT PLAN 'A'
A	APRIL 5, 2022	REVISE LEGEND

METRIC: DISTANCES AND COORDINATES SHOWN ON THIS PLAN ARE IN METRES AND CAN BE CONVERTED TO FEET BY DIVIDING BY 0.3048.



KEYMAP (NOT TO SCALE)

DRAFT PLAN OF SUBDIVISION

SECTION 51, PLANNING ACT

- | | |
|-----------------------------------|-------------------------------|
| A) AS SHOWN ON THE DRAFT PLAN | G) AS SHOWN ON THE DRAFT PLAN |
| B) AS SHOWN ON THE DRAFT PLAN | H) MUNICIPAL PIPED WATER |
| C) AS SHOWN ON THE DRAFT PLAN | I) SANDY LOAM |
| D) AS SHOWN ON THE LAND USE TABLE | J) AS SHOWN ON THE DRAFT PLAN |
| E) AS SHOWN ON THE DRAFT PLAN | K) FULL MUNICIPAL SERVICES |
| F) AS SHOWN ON THE DRAFT PLAN | L) AS SHOWN ON THE DRAFT PLAN |

SITE INFORMATION

SITE AREA

TOTAL SITE AREA: 3.97 HA

PARKING

RESIDENTIAL (DETACHED, SEMI-DETACHED):	REQUIRED	2.0 P/UNIT
RESIDENTIAL (TOWNHOUSES):	1.0 P/UNIT	
MIXED-USE:	1.0 P/UNIT	
RETAIL:	3 P/100M ² GFA	

SETBACKS

	F.Y.	C.Y.	S.Y.	R.Y.
DETACHED	4.5M	2.4M	1.2M	7.5M
SEMI-DETACHED	4.5M	2.4M	1.2M	7.5M
TOWNHOUSES	4.5M	2.4M	1.2M	-
MIXED-USE	1.8M	1.8	0M	-

DEVELOPMENT STATISTICS

RESIDENTIAL UNITS

DETACHED:	7
SEMI-DETACHED:	4
TOWNHOUSES:	55
MIXED-USE:	24
TOTAL:	90

PARKING

	REQUIRED	PROVIDED
RESIDENTIAL:	87	122
VISITOR:	22	45
COMMERCIAL:	36	38
TOTAL:	145	205

OPEN SPACE

CENTRAL PARK	0.134 HA
BARN PLAZA	0.085 HA

LAND CONVEYANCES

EMBANKMENT	0.313 HA
FUTURE ROAD WIDENING	0.097 HA

BLOCK USAGE

BLOCK 1	MIXED USE
BLOCK 2	MIXED USE
BLOCK 3	MIXED USE
BLOCK 4	STACKED TOWNS
BLOCK 5	HERITAGE HOUSE
BLOCK 6	STACKED TOWNS
BLOCK 7	DETACHED & SEMI DETACHED
BLOCK 8	TOWNHOMES
BLOCK 9	TOWNHOMES
BLOCK 10	MIXED USE BARN STRUCTURE
BLOCK 11	EMBANKMENT
BLOCK 12	FUTURE ROAD WIDENING
BLOCK 13	COMMON ELEMENT

OWNERS AUTHORIZATION

WE BEING THE REGISTERED OWNERS OF THE SUBJECT LANDS HEREBY AUTHORIZE FOTENN PLANNING & DESIGN TO PREPARE A DRAFT PLAN OF SUBDIVISION AND TO MAKE APPLICATION TO THE TOWN OF COBURG FOR APPROVAL THEREOF.

DATE: _____ SIGNED: KANE,RUTH,DEBORAH Digitally signed by KANE,RUTH,DEBORAH,1167009111 Date: 2022.04.21 23:32:42 -0400

RUTH DEBORAH KANE
540 KING STREET EAST
COBURG

SURVEYOR'S CERTIFICATE

I HEREBY CERTIFY THAT THE BOUNDARIES OF THE LAND TO BE SUBDIVIDED AND THEIR RELATIONSHIP TO THE ADJACENT LANDS ARE ACCURATELY AND CORRECTLY SHOWN ON THIS PLAN.

DATE: April 21, 2022 SIGNED: Merrill McLean

MERRILL MCLEAN
ONTARIO LAND SURVEYOR
DPP SURVEYORS
1101 BOUNDARY RD.
OSHAWA, ON L1J 8P8


DRAFT PLAN OF SUBDIVISION
540 KING STREET
PART OF LOT 10, CONCESSION A
GEOGRAPHIC TOWNSHIP OF HAMILTON
TOWN OF COBURG
COUNTY OF NORTHUMBERLAND

SCALE: 1 : 500 JOB NO. P2020-001 DESIGNED: TK DRAWING NO.

CHECKED: MDM DATE: APRIL 12, 2022 DRAWN: TK

CLIENT:

SUNNYSIDE VILLAGE INC.



10
A

PART 1, PLAN 39R-3698
P.I.N. 51102-0223

KING STREET EAST

November 27, 2023

Anne Taylor Scott

Director, Development and Design
The Corporation of the Town of Cobourg
55 King Street West
Cobourg, ON, K9A 2M2

**RE: 540 King Street East
Proposal for Zoning By-Law Amendment, Draft Plan of Subdivision, Draft Plan of Condominium
- Resubmission**

Fotenn Planning + Design has been retained by Sunnyside Village Inc. to prepare revised applications for Zoning By-law Amendment and Draft Plan of Subdivision for the subject lands at 540 King Street East in the Town of Cobourg. Please find enclosed the following materials for resubmission to the Town of Cobourg with regards to the applications noted:

- / Comments matrix in response to staff comments from first submission;
- / Revised concept plan, prepared by Fotenn Consultants, dated September 2023;
- / Functional Servicing Report, prepared by D.M. Willis, dated August 2023;
- / Environmental Impact Study, prepared by Pinchin Ltd., November 21, 2023;
- / Revised Draft Zoning By-law Amendment; and
- / Revised Draft Plan of Subdivision.

Applications for Zoning By-law Amendment and Draft Plan of Subdivision were initially submitted to the Town of Cobourg in May 2022 for a redevelopment proposal containing 90 residential units, mixed-use and open space uses. The submission of these applications was made in accordance with the complete submission requirements provided by the Town on November 21, 2019. The above noted applications were deemed complete by the Town of Cobourg on July 7, 2022.

On September 19th, 2022 a statutory public meeting was held with the Town of Cobourg to present the proposed development to the community. On February 9, 2023, comments on the application were received from Planning staff at the Town of Caledon.

Following the public meeting and the receipt of formal comments, our team had several meetings with Town of Cobourg Planning Staff to discuss the key planning issues. Subsequently a revised concept plan, technical studies and draft zoning by-law amendment was prepared in response to discussions and direction from the client. A comments matrix which addresses technical Staff comments from the first submission has been prepared and included as part of this complete resubmission package. The following section provides additional commentary on planning-related items as identified by staff.

Changes to Concept

The revised concept sees several changes which has been reflected in the updated draft zoning by-law and associated technical studies. Most significantly, the revised concept sees the removal of mixed-uses at the King Street East frontage and replacement with residential uses in the form of stacked townhouses. As a result, there

have been changes made to the wider development site area. The revised concept now proposes a total of 102 residential units with 176 parking spaces. The following list outlines the major revisions to the concept plan.

- / Mixed-use buildings at King Street East frontage have been changed to stacked townhouses;
- / Removal of commercial parking spaces at King Street East frontage;
- / Minor configuration changes to townhouse and detached garage layout;
- / Increased open space area at the Central Park;
- / Placing the barn in a future development zone until plans for redevelopment have been confirmed;
- / Revised environmental buffer to the restoration area; all development and grading is located outside of the environmental buffer and road allowance.

Population Density

Staff identified the following planning comments as they relate to the Zoning By-law Amendment and Draft Plan of Subdivision applications:

7. The Multiple Residential Four (R4) section of the By-law references density for subject lands. Please ensure the population density calculations are included and discussed in the Planning Justification Report (PJR).

12. Please ensure the population density calculations are included as part of the County, Town of Cobourg Official Plan and Zoning By-law discussions. The development complies with the proposed population projections per County and Town Official Plans.

Based on the new total of 102 residential units, the revised concept now proposes a density of 28.7 units per hectare (when calculated with a site area which subtracts the future road widening area only). The net density is 26.3 units per hectare (when calculated with a site area which subtracts the future road widening area only). Both density calculations meet the minimum density requirement for medium density residential development.

	Total Area	Density
Net Area (minus embankment and future road widening)	$3.97 - 0.327 - 0.097 = 3.546$ ha	28.7 units / ha
Net Area (minus future road widening)	$3.97 - 0.097 = 3.873$ ha	26.3 units / ha

As per Section 3.4.3.3, the density range for Medium Density residential development is as follows:

“3.4.3.3 ii) Medium Density

a) 20 units per net hectare (8 units per net acre) minimum

b) 50 units per net hectare (20 units per net acre) maximum”

The proposed net density as calculated above is within the acceptable range of the Medium Density category of residential development and is consistent with the Official Plan.

Parking Requirements

The following chart sets out the revised required and provided parking rates for the proposed development, as per Section 6.1.1 of the Zoning By-law. The proposed development meets all required parking standards.

Regulation	Requirement	Provided	Compliance
Detached, Semi-Detached: 2 spaces per dwelling unit	22 spaces required (11 detached + semi-detached units)	176 provided	Yes
Townhouse: 1.5 spaces per dwelling unit	138 spaces required (92 townhouse units)		

Since the revised concept proposes only residential uses, there is no longer a requirement for visitors parking. However visitors parking spaces have been incorporated throughout the development site. The parking strategy for the development site is based on the entire development, rather than on a per-block basis, as such, the development site is in compliance with zoning requirements for parking. It should be noted that while the townhouse portion at Blocks A, B, and C contains a total of 32 units and requirement for 48 parking spaces, there are only 44 garages provided in the dedicated rear parking area. The remaining 4 required spaces for these blocks are provided alongside the internal road network.

Draft Zoning By-law

Please refer to the revised Draft Zoning By-law for the updated zoning amendment approach. As discussed with Planning Staff, the majority of the residential blocks have been proposed to be rezoned to the Residential Four (R4) Exception Zones. In total there will be 3 site-specific R4 Zones, each with appropriate site-specific provisions that are suitable for the respective blocks. The existing residential farmhouse is proposed to be rezoned to a site-specific Residential 2 Exception zone, as it was deemed most appropriate for the site. The heritage-recognized barn is proposed to be rezoned to a Development (D) zone, until the intended future use is determined. The proposed Central Park and Barn Parkette will be rezoned to the Open Space (OS) zone. The environmental restoration area to the west of the site will be rezoned as Environmental Constraint (EC) zone.

The zoning matrix below sets out the proposal's compliance against the R4 zone (for Blocks A, B, C, D, E, F, G, H, I, J, K, M, N, O, P, Q, R, S, T, U V).

Provision	Requirement	Proposed R4-X1	Proposed R4-X2	Proposed R4-X3
Permitted Use	Public Use Residential Use	Residential	Residential	Residential
Permitted Accessory Uses	i) Accessory use to the Permitted uses under section 10.1.1 ii) Home occupation use iii) One bed and breakfast establishment	N/A		
Permitted buildings and structures	i) one unit of a semi-detached dwelling on one lot ii) one semi-detached dwelling on one lot iii) one duplex dwelling on one lot iv) one triplex dwelling on one lot v) one converted dwelling on one lot vi) one four-plex dwelling on one lot vii) townhouse dwelling including a townhouse dwelling for senior citizens' and / or the disabled viii) one multiple dwelling on one lot including a multiple dwelling for senior citizens and/or the disabled	Townhouse dwellings Multiple dwelling including stacked townhouse dwellings	Single detached dwelling Multiple dwelling including stacked townhouse dwellings	Multiple dwelling including stacked townhouse dwellings

Provision	Requirement	Proposed R4-X1	Proposed R4-X2	Proposed R4-X3	
	ix) one rooming or boarding house containing no more than 10 guest rooms on one lot x) one apartment dwelling including apartments for senior citizens / and or the disabled xi) buildings and structures for public uses in accordance with the provisions of Section 5.3.2 xii) accessory buildings and structures for the permitted uses				
Lot Area (min)	One unit of semi-detached dwelling	278 m ²	One unit of a townhouse dwelling: 178 m ²	One single-detached: 300 m ²	One unit of a townhouse dwelling: 123 m ²
	One semi-detached dwelling on one lot	557 m ²	One multiple dwelling or stacked townhouse dwelling: N/A	One unit of a semi-detached dwelling: 218 m ²	One multiple dwelling or stacked townhouse dwelling: N/A
	One triplex building, fourplex building, converted building, rooming or boarding house, or multiple dwelling	650 m ²		One unit of a townhouse dwelling: 143 m ²	
	Townhouse dwelling	215 m ²		One multiple dwelling or stacked townhouse dwelling: N/A	
Lot Frontage (min)	One unit of semi-detached dwelling	9 m	One townhouse dwelling: 6 m	One single-detached: 11 m	One unit of a townhouse dwelling: 6 m
	One semi-detached dwelling on one lot or one duplex building on one lot	18 m	Stacked townhouse: 24 m	One unit of a semi-detached dwelling: 8.5 m	One multiple dwelling or stacked townhouse dwelling: N/A
	One triplex building, fourplex building, converted building, rooming or boarding house, or multiple dwelling	18 m		One unit of a townhouse dwelling: 6 m	
	Townhouse dwelling which does not front onto a public street	30 m		One multiple dwelling or stacked townhouse dwelling: N/A	
	Townhouse dwelling where each townhouse units fronts onto a public street	6.5 m			

Provision	Requirement	Proposed R4-X1	Proposed R4-X2	Proposed R4-X3																		
Lots to Front on Public Road	<p>Notwithstanding the requirements of Section 5.11.1, a building or structure may be situated or erected on a lot which:</p> <p>i) fronts upon an assumed public street provided such building or structure is set back to meet or exceed the established building line, recognizes any road widenings to the Town's satisfaction, and is in compliance with any other requirements of this By-law; or,</p> <p>ii) is within a registered plan of subdivision, in accordance with the provisions of a subdivision agreement in respect of such plan of subdivision, notwithstanding that the roads within such plan of subdivision have not been assumed and are not being maintained by the Municipality; or,</p> <p>iii) is within a registered plan of subdivision which has been approved, after the adoption of this By-law, with road allowances of greater than 15 m (50 ft), but less than 20 m (66 ft); or,</p> <p>iv) fronts on a right-of-way that has a minimum 10 m (33 ft) width.</p>	Notwithstanding Section 5.11.2, for the purpose of lot frontage, the front lot line shall be the lot line abutting a private right-of-way with a minimum width of 6 m.																				
Lot Coverage (max)	40%	72%	40% for single-detached and semi-detached dwellings 56% for townhouses and stacked townhouse	45%																		
Floor Area per Dwelling Unit	<table border="1"> <tr> <td>Bachelor unit</td> <td>28 m²</td> </tr> <tr> <td>One bedroom unit</td> <td>42 m²</td> </tr> <tr> <td>Two bedroom unit</td> <td>56 m²</td> </tr> <tr> <td>Three bedroom unit</td> <td>70 m²</td> </tr> <tr> <td>Each additional bedroom</td> <td>10 m²</td> </tr> <tr> <td>Dwelling, Senior bachelor</td> <td>27 m²</td> </tr> <tr> <td>Dwelling, Senior one bedroom</td> <td>40 m²</td> </tr> <tr> <td>Dwelling, Senior two bedroom</td> <td>48 m²</td> </tr> <tr> <td>Dwelling, Senior three bedroom</td> <td>62 m²</td> </tr> </table>	Bachelor unit	28 m ²	One bedroom unit	42 m ²	Two bedroom unit	56 m ²	Three bedroom unit	70 m ²	Each additional bedroom	10 m ²	Dwelling, Senior bachelor	27 m ²	Dwelling, Senior one bedroom	40 m ²	Dwelling, Senior two bedroom	48 m ²	Dwelling, Senior three bedroom	62 m ²	N/A – site specific zoning will remove this provision		
Bachelor unit	28 m ²																					
One bedroom unit	42 m ²																					
Two bedroom unit	56 m ²																					
Three bedroom unit	70 m ²																					
Each additional bedroom	10 m ²																					
Dwelling, Senior bachelor	27 m ²																					
Dwelling, Senior one bedroom	40 m ²																					
Dwelling, Senior two bedroom	48 m ²																					
Dwelling, Senior three bedroom	62 m ²																					
Front yard (min)	The established building line, or where NA, 6m	4.5 m For the purpose of R4-X1, the Front Yard shall be considered the yard extending across the full width of the lot or zone which contains the main front feature.	4.5 m	4.5 m																		

Provision	Requirement	Proposed R4-X1	Proposed R4-X2	Proposed R4-X3
		For lots fronting onto King Street, the minimum front yard shall be 1.8m.		
Rear yard (min)	7m	7 m For multiple buildings/stacked townhouses that do not have individual rear yard amenities, they shall have a common outdoor amenity area of 19m ² area (minimum).	6 m Townhouse or stacked townhouse: 5.4 m	5 m
Interior side yard	i) one unit of a semi-detached dwelling, or a townhouse unit	No interior side yard shall be required between the common vertical wall dividing one dwelling unit from another. The side yard on the other side of the unit shall be 1.5 m min and 1m for each additional storey	1.5 m No interior side yard shall be required between the common vertical wall dividing one unit from another.	1.5 m No interior side yard shall be required between the common vertical wall dividing one unit from another.
	ii) duplex building; one semi-detached building on one lot; one converted, two unit building	2.5 m minimum for each interior side yard		
	iii) one triplex, an apartment building, a fourplex building, a multiplex building, one converted building with more than two residential units or a rooming and boarding house	3.65 minimum		
Exterior side yard	Established building line, or where not applicable, 6 m	3 m Accessory structures from the wall of the building to the lot line shall have a 0 m exterior side yard setback	1.6 m	2.5 m
Distance between exterior walls of townhouse buildings	Minimum distance between exterior walls of any 2 groups of townhouse dwellings on one lot shall be: i) where both ends of the group are one storey: 3 m ii) in all other circumstances: 5 m	3.0 m	3.0 m	3.0 m

Provision	Requirement	Proposed R4-X1	Proposed R4-X2	Proposed R4-X3
Distance between buildings (apartments, converted buildings or multiple buildings)	The minimum distance between any two apartment buildings, converted buildings or multiple buildings located on one lot shall be a measurement equivalent to the average height of the two buildings; however where neither external wall facing the other building contains the window of a habitable room the distance may be reduced to one half the average height of the two buildings	3.0 m	3.0 m	3.0 m
Landscaped open space (min)	35% of lot	20%	33%	Greater than 35%
Building height (max)	3 storeys	3 storeys	3 storeys	3 storeys
Regulations for accessory buildings and structures	Private garages and other accessory buildings / structures not attached to the main building shall: i) not be used for human habitation ii) not be built closer to the front lot line than the main building on the lot iii) have a minimum exterior side yard abutting the street line of 6m for a detached parking garage on a corner lot. For a detached accessory structure that is not intended for the storage or parking of a motor vehicle, boat storage, snowmobile, and does not have an associated driveway, a minimum 1 m exterior side yard may be permitted. iv) have a minimum interior side yard of 1m. semi detached garages may be centered on a mutual side lot line v) have a minimum rear yard of 1m vi) not exceed 4.5 m in height vii) not exceed 8% coverage of the lot area, provided that the coverage of all buildings on the lot shall not exceed 40% of the lot area viii) not be located within 1.5m of any other building or structure on the lot	Notwithstanding 10.1.19 iii), detached garages shall have a minimum exterior side yard of 0m. Notwithstanding 10.1.19 iv), detached garages shall have an interior side yard of 0 m. Notwithstanding 10.1.19 vii), detached garages shall not exceed 18% of the lot area.	Notwithstanding 10.1.19 iii), detached garages shall have a minimum exterior side yard abutting the street line of 5.7m for a detached garage on a corner lot. Notwithstanding 10.1.19 v), detached garages shall have a minimum rear side yard of 0m.	N/A

The zoning matrix below sets out the proposal's compliance against the R2 Zone (for the heritage farm house).

Provision	Requirement	Proposed R2-X1
Permitted Use	Group home use Public use Residential use	Residential
Permitted Accessory Use	i) Accessory use to the Permitted uses under section 8.1.1 ii) day nursery use home occupation use one bed and breakfast establishment	N/A
Permitted Buildings and Structures	i) one single detached dwelling on one lot	Existing single detached building

	ii) buildings and structures for public uses in accordance with the provisions of Section 5.3.2 iii) accessory buildings and structures for the permitted uses	
Lot Area (min)	i) 700 m ² minimum where sanitary sewers are not available ii) 465 m ² minimum where sanitary sewers are available	855 m ²
Lot Frontage (min)	i) 20 m minimum where sanitary sewers are not available ii) 15 m minimum where sanitary sewers are available	29 m
Lots to Front on Public Road	Notwithstanding the requirements of Section 5.11.1, a building or structure may be situated or erected on a lot which: i) fronts upon an assumed public street provided such building or structure is set back to meet or exceed the established building line, recognizes any road widenings to the Town's satisfaction, and is in compliance with any other requirements of this By-law; or, ii) is within a registered plan of subdivision, in accordance with the provisions of a subdivision agreement in respect of such plan of subdivision, notwithstanding that the roads within such plan of subdivision have not been assumed and are not being maintained by the Municipality; or, iii) is within a registered plan of subdivision which has been approved, after the adoption of this By-law, with road allowances of greater than 15 m (50 ft), but less than 20 m (66 ft); or, iv) fronts on a right-of-way that has a minimum 10 m (33 ft) width.	
Lot Coverage (max)	40%	34.2%
Floor Area (min)	80 m ²	Greater than
Front yard (min)	The established building line, or where not applicable, 6m	4.6 m
Rear yard (min)	7 m	Heritage house: 2.9 m
Interior side yard	i) The minimum width shall be 1 m (3.3 ft.) plus 0.6 m (2 ft.) for each additional storey above the first storey for each interior side yard;	2.8 m
Exterior side yard	The established building line, or where not applicable, 6m	4.3 m
Landscaped open space (min)	30%	Greater than 30%
Building height (max)	2 storeys	2 storeys
Regulations for detached accessory buildings and structures	Private garages and other accessory buildings and structures not attached to the main building shall: i) not be used for human habitation; ii) not be built closer to the front lot line than the main building on the lot; iii) have a minimum exterior side yard abutting the street line of 6 m (20 ft.) for a detached parking	Comply with provisions.

	<p>garage on a corner lot. For a detached accessory structure that is not intended for the storage or parking of a motor vehicle, boat storage, snowmobile, etc. and does not have an associated driveway, a minimum 1 m (3.3 ft.) exterior side yard may be permitted;</p> <p>iv) have a minimum interior side yard of 1 m (3.3 ft.). Semi-detached garages may be centred on a mutual side lot line;</p> <p>v) have a minimum rear yard of 1 m (3.3.ft);</p> <p>vi) not exceed 4.5 m (15 ft.) in height;</p> <p>vii) not exceed 8% coverage of the lot area, provided that the coverage of all buildings on the lot shall not exceed 40% of the lot area;</p> <p>viii) not be located within 1.5 m (5 ft.) of any other building or structure on the lot.</p>	
--	---	--

We trust that this resubmission package for the above-noted applications address the comments raised by Town Staff. Should you have any questions or comments, please do not hesitate to contact the undersigned at 416.789.4530 x 16, or via e-mail at maestre@fotenn.com.

Respectfully submitted,

Sincerely,



Jennifer Maestre, MPL, RPP, MCIP
 Associate
Fotenn Planning + Design



Yuki Naganuma
 Planner
Fotenn Planning + Design